

### PUBLIC NOTICE TOWN OF WINTER PARK PLANNING COMMISSION & TOWN COUNCIL PRELIMINARY PLAT AND MAJOR SITE PLAN

Applicant: Michael Dire, Design Practice

Property Owner: Gondola Townhomes, LLC

Case Number: PLN24-005 (Preliminary Plat) AND PLN23-095 (Major Site Plan)

Physical Address of Property for Which the Application Approval is Requested: 185 Vasquez Road, Winter Park, CO

Legal Description & Vicinity Map of Property for Which the Application Approval is Requested: See Exhibit A attached.

**Description of Request:** An application for a preliminary plat and major site plan for a proposed 19 unit townhome development on approximately 1.25 acres.

Applicable Provision(s) of the Unified Development Code (UDC): § 5-E-1 G. Major Site Plan and § 5-D-4 Preliminary Plat

Additional information is available at this link: https://wpgov.com/current-development-projects/

Public Hearings at Winter Park Town Hall, 50 Vasquez Road and online via Zoom are scheduled for:

### Planning Commission, Tuesday, August 27, 2024 at 8:00 A.M. Town Council, Tuesday, September 3, 2024 at 5:30 PM

Members of the public wishing to make comment regarding the application may do so at the scheduled hearings, or write to Shelia Booth, Contracted Planner, Town of Winter Park, P.O. Box 3327, Winter Park, CO 80482, or send comments by email to <a href="mailto:sbooth@planstrategize.com">sbooth@planstrategize.com</a>. For comments to be included within the digital packet, they must be submitted by 5:00 P.M. on the Wednesday before the hearing.


The Zoom link will be made available in the Planning Commission and Town Council full agendas, which will be published by end of day the Friday before each hearing at:

https://wpgov.com/our-government/agendas-minutes/

The meeting will be broadcast via Zoom and public comment can be made by those attending. If there are technical difficulties with Zoom, public comment via Zoom will not be available and the meeting will continue in person.

### Exhibit A - Legal Description and Location Map

A PARCEL OF LAND BEING A PART OF THE NORTHWEST QUARTER (NW 1/4) OF SECTION 33, TOWNSHIP 1 SOUTH, RANGE 75 WEST OF THE 6TH PRINCIPAL MERIDIAN, TOWN OF WINTER PARK AND COUNTY OF GRAND, STATE OF COLORADO



15.067 SF PAVED SURFACE AREA

PROPOSED SNOW

STORAGE

SETBACK -

**EASEMENT** 

REC. NO. 2002-013714

RECIPROCAL ENCROACHMENT

LOW PLANTER

BOX, TYP.

CULLEN PARCEL UTILITY

RELOCATED UTILITY POLE

REC. NO. 2002-013717 -

AND UTILITIES -

PROPOSED SNOW

REC. NO. 2002-013717

1. NO DISTURBANCE, GRADING, OR REMOVAL FO SIGNIFICANT NATURAL FEATURES AND

VEGETATION WILL OCCUR BEYOND THE "LIMIT OF DISTURBANCE" LINE, AS SHOWN IN THIS PLAN.

2. THE "LIMIT OF DISTURBANCE" LINE SHALL BE DELINEATED PRIOR TO CONSTRUCTION WITH FLAGS,

ROPING, FOUR FOOT (4') TALL ORANGE CONSTRUCTION FENCING, OR OTHER ACCEPTABLE MEANS.

RECIPROCAL ENCROACHMENT EASEMENT

**PROTECTION NOTES:** 

STORAGE 2,678 SF

TURNING DIAGRAM FOR CAR ENTRY AND EXIT

WITH 5' BACK OUT AREA

1 SITE PLAN 1" = 20'-0"

LOT 1 UTILITY EASEMENT

REC. NO. 2002-013717

PARKING EASEMENT

REC. NO. 2002-013717

### **BUILDING UNIT CALCULATIONS**

**BLDG A - UNIT TYPE '1' - AREA CALCS** FINISHED 476 SF FINISHED 469 SF GARAGE 451 SF GARAGE 459 SF PATIO 142 SF PATIO 164 SF LEVEL 2: LEVEL 2: FINISHED 997 SF FINISHED 960 SF DECKS 103 SF DECKS 95 SF LEVEL 3: LEVEL 3: FINISHED 981 SF DECKS 73 SF DECKS 54 SF

TOTAL BLDG A - TYPE '1' UNITS = 2 FINISHED GROSS FINISHED 2,476 SF X 2 = **4952 SF** 2,417 SF X 3 = **7251 SF** 318 SF X 2 = **636 SF** DECKS/PATIO 313 SF X 3 = **939 SF** 451 SF X 2 = 902 SF

**BLDG B - UNIT TYPE '3' - AREA CALCS** BLDG B - UNIT TYPE '4' - AREA CALCS LEVEL 1: FINISHED 335 SF FINISHED 337 SF GARAGE 543 SF GARAGE 557 SF PATIO 193 SF PATIO 206 SF LEVEL 2: LEVEL 2: FINISHED 1014 SF FINISHED 978 SF DECKS 156 SF DECKS 163 SF LEVEL 3: LEVEL 3:

FINISHED 1019 SF

**BLDG C - UNIT TYPE '3' - AREA CALCS** 

DECKS 69 SF

TOTAL BLDG B - TYPE '3' UNITS = 2 GROSS FINISHED 2,476 SF X 2 = **4952 SF** 2,314 SF X 3 = **6942 SF** DECKS/PATIO 421 SF X 3 = **1263 SF** 318 SF X 2 = **636 SF** GARAGE 557 SF X 3 = **1671 SF** 543 SF X 2 = **1086 SF** 

FINISHED 1001 SF

BLDG C - UNIT TYPE '4' - AREA CALCS

TOTAL BLDG D - TYPE '2' UNITS = 2

DECKS/PATIO 285 SF X 2 = **570 SF** 

FINISHED

2,273 SF X 2 = **4546 SF** 

557 SF X 2 = **1114 SF** 

2,423 SF X 2 = **4846 SF** 

466 SF X 2 = **932 SF** 

DECKS 52 SF

LEVEL 1: LEVEL 1: FINISHED 335 SF FINISHED 335 SF GARAGE 541 SF GARAGE 557 SF PATIO 196 SF PATIO 189 SF LEVEL 2: LEVEL 2: FINISHED 989 SF FINISHED 962 SF DECKS 157 SF DECKS 149 SF LEVEL 3: LEVEL 3: FINISHED 976 SF DECKS 65 SF DECKS 54 SF

TOTAL BLDG C - TYPE '3' UNITS = 2 GROSS FINISHED 2,328 SF X 2 = **4656 SF** FINISHED 418 SF X 2 = **836 SF** DECKS/PATIO 392 SF X 2 = **784 SF** 541 SF X 2 = **1082 SF BLDG D - UNIT TYPE '1' - AREA CALCS** 

LEVEL 1: FINISHED 473 SF GARAGE 466 SF GARAGE 458 SF PATIO PATIO 136 SF LEVEL 2: FINISHED 999 SF FINISHED 964 SF DECKS 103 SF DECKS 95 SF LEVEL 3: LEVEL 3: FINISHED 1014 SF FINISHED 986 SF DECKS 73 SF DECKS 54 SF

TOTAL BLDG D - TYPE '1' UNITS = 2 2,480 SF X 2 = **4960 SF** GROSS FINISHED 318 SF X 2 = **636 SF** 458 SF X 2 = **916 SF** 

TOTAL UNITS = 18 GROSS FINISHED AREA = 43,105 SF DECK AREA = 6,300 SF GARAGE AREA = 9,078 SF

STORM DRAIN

Graphic Scale: 1 inch = 20 feet

SNOW STORAGE TABLE

PROPOSED ASPHALT AND CONCRETE

REQUIRED SNOW STORAGE (25%)

PROPOSED SNOW STORAGE

TOTAL PERCENTAGE OF SNOW STORAGE

SQ. FT.

3,767

3,822

TOP BACK

OF CURB

RELOCATED LIGHT POLE

DRIVEWAY TO BE SETBACK 7 FT

30'X10' SIGHT TRIANGLE, TYP.

**BOTH SIDES OF DRIVEWAY** 

FROM ADJACENT PROPERTY LINE

BUILDING COVERAGE RA	TIO TABL	. <b>L</b>	
	SQ. FT.	ACRES	% OF SITE
TOTAL PARCEL SIZE	54,313	1.25	100.00%
EXISTING IMPERVIOUS AREA			
EXISTING GRAVEL PAVING	9,225	0.21	17%
EXISTING CONCRETE	290	0.01	1%
EXISTING BUILDINGS	5,124	0.12	9%
TOTAL TOTAL EXISTING IMPERVIOUS AREA	14,639	0.34	27%
EXISTING IMPERVIOUS AREA TO BE REMOVED	SQ. FT.	ACRES	% OF SITE
EXISTING BUILDINGS TO BE REMOVED	5,124	0.12	9%
TOTAL IMPERVIOUS AREA TO BE REMOVED	9,515	0.22	18%
PROPOSED IMPERVIOUS AREA	SQ. FT.	ACRES	% OF SITE
PROPOSED BUILDINGS	19,690	0.45	36%
PROPOSED ASPHALT PAVING	15,067	0.35	28%
PROPOSED CONCRETE SIDEWALK	301	0.01	0.01%
PROPOSED CONCRETE - PUBLIC ART	314	0.01	0.01%
TOTAL PROPOSED IMPERVIOUS AREA	35,208	0.81	65%

NUMBER OF PROPOSED TOWNHOUSE UNITS = 18 TYPE 1: 5 BED, 4 BATH; TYPE 2: 5 BED, 4 BATH; TYPE 3: 4 BED, 3 BATH; TYPE 4: 4 BED, 3 BATH

36 PROPOSED PARKING SPACES 18 UNITS WITH 2 OR MORE BEDROOMS X 2 = 36 SPACES ALL 36 SPACES ARE ENCLOSED

2 SPACES PER 2 BEDROOM OR MORE UNIT PER UDC SEC. 3-H-3 TABLE 3-H-3-1

OPTION FOR 4 SURFACE GUEST PARKING SPACES

1 ADA VAN ACCESSIBLE SPACE PROVIDED PER SEC. 208.2.3.2 & 502 OF THE 2010

**BLDG A - UNIT TYPE '2' - AREA CALCS** 

PRACTI DESIGN PRACTICE INC 2842 W 44th Denver CO 80211

www.designpracticedenver.com

info@designpracticedenver.com PHONE\_303 561 3000

No.	Desc.	Date

Drawn By:

Checked By: ZONING

MD

**SUBMITTAL** 

**ISSUE DATE** 

08/12/2024

SITE PLAN



3 BLDG A - 3D View 3





**TOWNHOMES** ANDING No. Desc. Date

DESIGN
PRACTICE\_INC
2842 W 44th
Denver CO 80211
www.designpracticedenver.com
info@designpracticedenver.com
PHONE\_303 561 3000

8

Drawn By: Checked By:

MD DP

ZONING SUBMITTAL

ISSUE DATE

08/12/2024

BLDG A - 3D

RENDERINGS

4 BLDG A - 3D View 4









# THE LANDING TOWNHOMES

DESIGN
PRACTICE\_INC
2842 W 44th
Denver CO 80211
www.designpracticedenver.com
info@designpracticedenver.com
PHONE\_303 561 3000

Desc. Da

No. Desc. Date

Drawn By: MD
Checked By: DP
ZONING

ZONING SUBMITTAL

1SSUE DATE 07/02/2024

BLDG B - 3D RENDERINGS



BLDG C - 3D View 4

2 BLDG C - 3D View 2

3 BLDG C - 3D View 3

1 BLDG C - 3D View 1







TOWNHOMES ANDING No. Desc. Date

DESIGN
PRACTICE\_INC
2842 W 44th
Denver CO 80211
www.designpracticedenver.com
info@designpracticedenver.com
PHONE\_303 561 3000

19

Drawn By: Checked By:

MD DP

ZONING SUBMITTAL

ISSUE DATE

07/02/2024

BLDG C - 3D

RENDERINGS



2 SITE - 3D View 2



1 SITE - 3D View 1

# THE LANDING TOWNHOMES

DESIGN

PRACTICE\_INC
2842 W 44th
Denver CO 80211
www.designpracticedenver.com
info@designpracticedenver.com
PHONE\_303 561 3000

No. Desc. Date

07/02/2024

ZONING SUBMITTAL


SITE - 3D RENDERINGS

Drawn By: Checked By:

25









## DESIGN PRACTICE\_INC 2842 W 44th Denver CO 80211 www.designpracticedenver.com info@designpracticedenver.com PHONE\_303 561 3000

## THE LANDING TOWNHOMES

No. Desc. Date

Drawn By: MD
Checked By: DP

ZONING SUBMITTAL

ISSUE DATE

07/02/2024

BLDG D - 3D RENDERINGS



### PRELIMINARY PLAT THE LANDING - TOWNHOMES

A PARCEL OF LAND BEING A PART OF THE NORTHWEST QUARTER (NW 1/4) OF SECTION 33, TOWNSHIP 1 SOUTH, RANGE 75 WEST OF THE 6TH PRINCIPAL MERIDIAN, CITY OF WINTER PARK AND COUNTY OF GRAND, STATE OF COLORADO SHEET 1 OF 2

### DEDICATION CERTIFICATE:

KNOW ALL MEN BY THESE PRESENTS: THAT GONDOLA TOWNHOMES, LLC A LIMITED LIABILITY COMPANY IS THE OWNER OF THAT REAL PROPERTY SITUATE IN THE TOWN OF WINTER PARK, GRAND COUNTY, COLORADO, MORE FULLY DESCRIBED AS FOLLOWS:

LOT 2, CULLEN MINOR PLAT ACCORDING TO THE PLAT THEREOF RECORDED AUGUST 23, 2023 UNDER RECEPTION NO. 2023-005301

THAT IT HAS CAUSED SAID REAL PROPERTY TO BE LAID OUT AND SURVEYED AS THE LANDING - TOWNHOMES, AND DOES HEREBY DEDICATE AND SET APART ALL THE STREETS, ALLEYS AND OTHER PUBLIC WAYS AND PLACES SHOWN ON THE ACCOMPANYING PLAT FOR THE USE OF THE PUBLIC FOREVER, AND DOES HEREBY GRANT TO THE TOWN OF WINTER PARK USE OF THOSE PORTIONS OF SAID REAL PROPERTY WHICH ARE INDICATED AS EASEMENTS ON THE ACCOMPANYING PLAT AS PERMANENT PUBLIC EASEMENTS.

IN WITNESS WHEREOF, GONDOLA TOWNHOMES, LLC, A COLORADO LIMITED LIABILITY COMPANY HAS CAUSED ITS NAME TO BE HEREUNDER SUBSCRIBED THIS \_\_\_\_\_\_ DAY OF \_\_\_\_\_\_\_, 20\_\_\_\_\_.

GONDOLA TOWNHOMES, LLC, A COLORADO LIMITED LIABILITY COMPANY
BY: , AS
STATE OF)
) SS COUNTY OF )
THE FOREGOING INSTRUMENT WAS ACKNOWLEDGED BEFORE ME THIS DAY OF, 20
WITNESS MY HAND AND OFFICIAL SEAL.
MY COMMISSION EXPIRES:
NOTARY PUBLIC

### **ESTOPPEL CERTIFICATE:**

WE, GONDOLA TOWNHOMES, LLC, A COLORADO LIMITED LIABILITY COMPANY, THE OWNER OF THE PROPERTY INCLUDED IN THE LANDING - TOWNHOMES, CERTIFY THAT THIS FINAL PLAT AND THE SUBDIVISION IMPROVEMENT AGREEMENT TO BE EXECUTED IN CONNECTION WITH THIS FINAL PLAT, IF REQUIRED, EMBODY THE ENTIRE AGREEMENT BETWEEN THE OWNER OF SAID PROPERTY AND THE TOWN OF WINTER PARK WITH REGARD TO THE SUBDIVISION OF SAID PROPERTY, AND THAT THE OWNER IS NOT RELYING UPON ANY OTHER REPRESENTATIONS, WARRANTIES, UNDERSTANDINGS, OR AGREEMENTS IN CONNECTION WITH ANY MATTER ENCOMPASSED BY THIS PLAT OR THE SUBDIVISION IMPROVEMENT AGREEMENT IF REQUIRED, EXCEPT AS SET FORTH ON THIS PLAT OR IN SAID SUBDIVISION IMPROVEMENT AGREEMENT.

GONDOLA TOWNHOMES, LLC, A COLORADO LIMITED LIABILITY COMPANY

BY:	
	, AS

### CERTIFICATE OF LIEN HOLDER/DEED OF TRUST HOLDER:


THE UNDERSIGNED HEREBY CERTIFIES THAT IT IS A LAWFUL LIENHOLDER/DEED OF TRUST HOLDER AS TO THE REAL PROPERTY DESCRIBED IN THIS FINAL PLAT, DOES HEREBY CERTIFY THAT IT ACCEPTS THE CONDITIONS AND RESTRICTIONS SET FORTH IN THIS FINAL PLAT, AND DOES HEREBY SUBORDINATE ITS INTERESTS IN THE PROPERTY DESCRIBED IN THIS FINAL PLAT TO THE FEE SIMPLE DEDICATIONS AND GRANTS OF EASEMENTS (IF ANY) HEREBY PROVIDED TO THE TOWN OF WINTER

GONDOLA TOWNHOMES, LLC, A LIMITED LIABILITY COMPANY

BY:			
	, AS		
STATE OF	) ) SS		
COUNTY OF	)		
	LIENHOLDER/DEED OF TRUST HOLDER WA	AS ACKNOWLEDGED BEFORE ME THIS [	AY OF
WITNESS MY HAND AND SEAL.			

WITNESS MY HAND AND SEAL:

NOTARY PUBLIC
MY COMMISSION EXPIRES:



SUBDIVIDER: GONDOLA TOWNHOMES, LLC 9557 PARADISE LN. BROOMFIELD, CO 80020

LAND SURVEYOR: POWER SURVEYING COMPANY, INC. 6911 BROADWAY DENVER, CO 80221 (303)-702-1617

DESIGNER/ENGINEER: FABRE ENGINEERING INC. 2063 PINON PL. ERIE, CO 80516 (720)-903-0048

### PLANNER'S CERTIFICATE:

I,\_\_\_\_\_\_\_, BEING A QUALIFIED PROFESSIONAL ENGINEER OR PLANNER, CERTIFY THAT THIS PLAT OF THE LANDING - TOWNHOMES HAS BEEN ENGINEERED, DESIGNED AND PLANNED IN ACCORDANCE WITH ALL APPLICABLE DESIGN STANDARDS AND OTHER REQUIREMENTS OF THE TOWN OF WINTER PARK SUBDIVISION REGULATIONS.

### MAYOR'S CERTIFICATE:

NICK KUTRUMBOS, MAYOR	-
ATTEST:	
DANIELLE JARDEE, TOWN CLERK	-

COMMISSION, WINTER PARK, COLORADO.

PLANNING COMMISSION CERTIFICATE:

APPROVED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_\_, 20\_\_\_ BY THE TOWN OF WINTER PARK PLANNING

DAVID BARKER, CHAIRPERSON

### **OUTLOT TABLE**

NAME	<u>AREA</u>	OWNERSHIP	MAINTENANCE
OUTLOT A	±9,108	H.O.A.	H.O.A.
OUTLOT B	±23,197	H.O.A.	H.O.A.

### NOTES:

EASEMENTS.

- 1. THE FOLLOWING IS A PARTIAL LIST OF DOCUMENTS UTILIZED IN THE PREPARATION OF THIS SURVEY:
  - A. GRAND COUNTY RECORDS, SECOND AMENDED FINAL PLAT, LOT 1, TEVERBAUGH-HEATON MINOR SUBDIVISION AND CULLEN SUBDIVISION EXEMPTION, RECEPTION NO. 2002-13714.
- B. AMENDED FINAL PLAT LOTS 1 AND 2, TEVERBAUGH-HEATON MINOR SUBDIVISION, RECEPTION NO. 2001012302.
  C. GRAND COUNTY SURVEYOR RECORDS, UNTITLED RAILROAD MAP.
- 2. POWER SURVEYING COMPANY, INC. RELIED UPON TITLE COMMITMENT FROM OLD REPUBLIC NATIONAL TITLE COMPANY ORDER NO. J60016033 WITH AN EFFECTIVE DATE OF SEPTEMBER 1, 2023 AT 2:47 P.M. FOR THE LEGAL DESCRIPTION, RIGHTS OF WAY AND
- BASIS OF BEARINGS: THE SOUTHEASTERLY LINE OF LOT 2, CULLEN MINOR PLAT IS ASSUMED TO BEAR SOUTH 41°45'47" WEST, A
  DISTANCE OF 125.01 FEET BETWEEN A FOUND #5 REBAR WITH 1.75" SQUARE COLLAR AT THE SOUTHWESTERLY END, AND A FOUND
- 4. SUBJECT PROPERTY IS CURRENTLY ZONED TOWN OF WINTER PARK "DESTINATION CENTER / D-C"

1.5" ILLEGIBLE ALUMINUM CAP AT THE NORTHEASTERLY END AS MEASURED AND SHOWN HEREON.

- 5. WET LANDS DELINEATION FLAGS WERE FOUND ON THE SUBJECT PROPERTY AND ARE SHOWN HEREON AND PER THE WET LAND DELINEATION REPORT FOR 185 VAXQUEZ DATED JULY 18, 2023 FROM APPLIED ECHOHYDRO PROVIDED BY THE CLIENT.
- 6. IMPROVEMENTS EXIST IN THE SUBJECT PROPERTY WHICH ARE NOT DEPICTED HEREIN PER TOWN OF WINTER PARK REQUEST.
- 7. FLOODPLAIN INFORMATION DEPICTED HEREIN WAS OBTAINED FROM FLOOD INSURANCE RATE MAP (FIRM) NO. 08049C0991C, EFFECTIVE DATE OF 01-02-2008, TOGETHER WITH THE ACCOMPANYING FIRMETTE.
- 8. NOTICE: ACCORDING TO COLORADO LAW, YOU MUST COMMENCE ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY WITHIN THREE YEARS AFTER YOU FIRST DISCOVER SUCH DEFECT. IN NO EVENT MAY ANY LEGAL ACTION BASED UPON ANY DEFECT IN THIS SURVEY BE COMMENCED MORE THAN TEN YEARS FROM THE DATE OF CERTIFICATION SHOWN HEREON.
- PROJECT BENCHMARK: NGS BENCHMARK "N 139" IS A BENCHMARK DISK IN A CONCRETE POST LOCATED 51' WEST OF THE CENTERLINE OF U.S. HIGHWAY 40, 98' EAST OF THE CENTERLINE OF THE RAILROAD TRACKS, STAMPED "N 139 1934" PUBLISHED NAVD 88 ELEVATION = 8438.43 U.S. SURVEY FEET

A) SITE BENCHMAKR #1 - A FOUND 2" ALUMINUM CAP STAMPED PLS 11415 FOUND AT THE NORTHEASTERLY CORNER OF OUTLOT B - NAVD88 ELEVATION IS 8814.78.

B) SITE BENCHMARK #2 - FOUND 1.5" ALUMINUM CAP STAMPED PLS 31942 LOCATED AT THE MOST SOUTHEASTERLY CORNER OF OUTLOT B - NAVD88 ELEVATION IS 8822.01.

- 10. DRY UTILITY EASEMENTS ("DUE") ARE HEREBY DEDICATED TO THE TOWN OF WINTER PARK AS SHOWN HEREON FOR THE INSTALLATION, MAINTENANCE, AND REPLACEMENT OF ELECTRIC, GAS, TELEVISION CABLE, TELECOMMUNICATIONS FACILITIES AND ALL SIMILAR PURPOSES. NO STRUCTURE SHALL BE PLACED OR CONSTRUCTED WITHIN ANY DUE EXCEPT AS NECESSARY FOR UTILITY OPERATIONS WHEN EXPLICITLY APPROVED BY THE TOWN.
- 11. TO ALLOW FOR ADEQUATE SNOW REMOVAL, NO STRUCTURE, INCLUDING UTILITY FACILITIES, SHALL BE PLACED WITHIN FIVE FEET OF A PUBLIC ROW UNLESS SPECIFICALLY EXEMPTED BY THE TOWN.
- 12. THE SUBJECT PROPERTY IS SUBJECT TO AN ENCROACHMENT LICENSE RECORDED AT REC. NO. \_\_\_\_\_\_ REQUIREING MAINTENANCE AND SNOW REMOVAL FOR THE CONCRETE WALKS WITHIN THE VASQUEZ ROAD RIGHT OF WAY AS SHOWN HEREON.
- 13. THE 15 FOOT WIDE STRIP OF LAND ALONG THE NORTH LINE OF THIS SUBDIVSION WAS LISTED ON LOT 2, CULLEN MINOR PLAT ACCORDING TO THE PLAT THEREOF RECORDED AUGUST 23, 2023 UNDER
- RECEPTION NO. 2023-005301 AS A 15.00 FOOT STRIP, WINTER PARK AND IS SHOWN AS BOOK 89 PAGE 140. BOOK 89 PAGE 140 IS NOT THE CORRECT DOCUMENT FOR THIS RIGHT OF WAY DEDICATION. THE ASSESSOR OFFICE WAS CONSULTED IN THIS MATTER AND THEY STATED THEY DO NOT KEEP TRACK OF THOSE DOCUMENTS. THIS SURVEYOR IS UNABLE TO DETERMINE WHAT RIGHTS THE PUBLIC HAS IN AND TOO THIS RIGHT OF WAY.
- 14. ON SITE ELECTRIC UTILITY EASEMENTS ARE HEREBY DEDICATED BY THIS PLAT IN THE LOCATIONS SHOWN HEREON AND ARE ESTABLISHED FOR INGRESS TO AND EGRESS FROM, THE INSTALLATION, REPAIR, REPLACEMENT, OPERATION AND MAINTENANCE OF PUBLIC UTILITIES, INCLUDING ELECTRIC LINES AND EQUIPMENT. NO PART OF A STRUCTURE (INCLUDING DECKS, OVERHANGS, FOOTERS, ETC) SHALL BE ALLOWED IN THE UTILITY EASEMENT OR CLOSER THAN TEN FEET (10') FROM ANY PRIMARY VOLTAGE POWER LINES OR WITHIN TEN FEET (10') AROUND ANY ABOVE GROUND EQUIPMENT. NO GAS LINE WILL BE PERMITTED CLOSER THAN FIVE FEET (5') TO ANY PRIMARY VOLTAGE LINES OR EQUIPMENT. NOTWITHSTANDING THE FOREGOING, UNDERGROUND COMMUNICATION FACILITIES SHALL NOT BE ALLOWED CLOSER THAN ONE FOOT (1') TO ANY POWER LINES AND ABOVE GROUND COMMUNICATION FACILITIES SHALL NOT BE CLOSER THAN TWO FEET (2') TO ANY ABOVE GROUND ELECTRIC FACILITIES. NO GRADE CHANGES (FILL OR CUT) IN EXCESS OF SIX INCHES (6") ARE PERMITTED IN THE UTILITY EASEMENT WITHOUT PRIOR WRITTEN AUTHORIZATION FROM MOUNTAIN PARKS ELECTRIC, INC. NO TREES OR BOULDERS MAY BE PLANTED OR PLACED WITHIN FIVE FEET (5') OF ANY POWER LINE OR ELECTRIC EQUIPMENT. ALL EQUIPMENT WILL HAVE A MINIMUM OF TEN FEET (10') OF CLEARANCE IN FRONT OF ANY OPENINGS OR EQUIPMENT DOORS.
- 15. ALL MULTI-USE BUILDINGS WITHIN THIS SUBDIVISION THAT HAVE ELECTRIC METERS ON ONE UNIT (GANG METERING) WILL BE INSTALLED UNDER A PERMANENT STRUCTURAL ELEMENT THAT PROTECTS THE METERS AND WILL HAVE A PERPETUAL NON-EXCLUSIVE UTILITY EASEMENT FOR THE PURPOSE OF CONSTRUCTING AND OPERATING THE ELECTRIC SUPPLY FOR DISTRIBUTION. ALL WIRES AND OTHER FACILITIES SUCH AS CONDUIT, SWITCHES AND METER BOXES BUT NOT INDIVIDUAL METERS, INSTALLED ON THE ABOVE-DESCRIBED LANDS SHALL BE THE PROPERTY OF THE LANDINGS TOWNHOMES HOA. ALL METERS SHALL BE THE PROPERTY OF MOUNTAIN PARKS ELECTRIC, INC.
- 16. INDIVIDUAL WATER, SEWER, AND FIRE SUPPRESSION LINES/SERVICE WILL BE REQUIRED FOR EACH TOWNHOME.
- 17. THIS PLAT IS SUBJECT TO THE 2020 WINTER PARK/DOWNTOWN MASTER PLAN [DESIGN GUIDELINES, 3.2.4 STREETSCAPE DESIGN; CONFLUENCE DISTRICT], AS A REFERENCE DOCUMENT FOR FUTURE OWNERS. THE DOWNTOWN MASTER PLAN INDICATES THE TOWN'S INTENT FOR A FUTURE ROUNDABOUT AT VASQUEZ ROAD AND LION'S GATE DRIVE WHEREBY RESIDENTS OF THIS PROJECT MAY LOSE USE OF FRONT YARD AREAS AND SIDEWALKS.
- 18. THE LANDING TOWNHOMES HOA WILL BE RESPONSIBLE FOR CLEARING AND MAINTAINING THE WALKS INDIVIDUAL TOWNHOMES WITHIN THE RIGHT-OF-WAY.

### SURVEYOR'S CERTIFICATION:

I, RICHARD B GABRIEL, A DULY REGISTERED LAND SURVEYOR IN THE STATE OF COLORADO, DO HEREBY CERTIFY THAT THIS PLAT OF THE LANDING - TOWNHOMES TRULY AND CORRECTLY REPRESENTS THE RESULTS OF A SURVEY MADE BY ME OR UNDER MY DIRECTION, AND THAT SAID PLAT COMPLIES WITH THE REQUIREMENTS OF TITLE 38, ARTICLE 51, COLORADO REVISED STATUTES, AND THAT THE MONUMENTS REQUIRED BY SAID STATUTE AND BY THE TOWN OF WINTER PARK SUBDIVISION REGULATIONS HAVE BEEN PLACED ON THE GROUND. THIS PLAT IS A TRUE AND ACCURATE REPRESENTATION OF SAID SURVEY.

RICHARD B. GABRIEL, COLORADO P.L.S. #37929
ON BEHALF OF POWER SURVEYING COMPANY, INC.

SHEET INDEX:


SHEET 2 - PRELIMINARY PLAT MAP


SHEET 1 - COVER SHEET, CERTIFICATES, AND NOTES





·mmmu.		
TYPE OF SUBMITTAL:	PRELIMINARY PLAT	
PREPARATION DATE:	JANUARY 5, 2024	
REVISION DATE:	MAY 1, 2024	
REVISION DATE:	JULY 2, 2024	
DRAWN BY: JRY	REVIEWED BY: RBG	
JOB NO. 23-174	DWG: 23-174 PP.dwg	
SHEE	T 1 OF 2	






### THE LANDING - TOWNHOMES MAJOR SITE PLAN

A PARCEL OF LAND BEING A PART OF THE NORTHWEST QUARTER (NW 1/4) OF SECTION 33, TOWNSHIP 1 SOUTH, RANGE 75 WEST OF THE 6TH PRINCIPAL MERIDIAN, TOWN OF WINTER PARK, COUNTY OF GRAND, STATE OF COLORADO

**185 VASQUEZ ROAD** 





## MES

THE LANDING TOWNHOME

185 VASQUEZ RD, WINTER PARK, CO 80482

No.	Desc.	Date

Drawn By: MD
Checked By: DP

ZONING SUBMITTAL

08/12/2024

LANDSCAPE PLAN

27


### THE LANDING - TOWNHOMES **MAJOR SITE PLAN**

A PARCEL OF LAND BEING A PART OF THE NORTHWEST QUARTER (NW 1/4) OF SECTION 33, TOWNSHIP 1 SOUTH, RANGE 75 WEST OF THE 6TH PRINCIPAL MERIDIAN, TOWN OF WINTER PARK, COUNTY OF GRAND, STATE OF COLORADO

**185 VASQUEZ ROAD** 


### LANDSCAPE PLANT LIST

### **ORNAMENTAL TREES** MATURE MATURE SIZE AND **COMMON NAME BOTANICAL NAME** SUN/SHADE HEIGHT WIDTH CONDITION **QUAKING ASPEN** POPULUS TREMULOIDES 20'-50' 20'-30' 1" CAL., B&B ASPL **QUAKING ASPEN** POPULUS TREMULOIDES 20'-50' 20'-30' 2" CAL., B&B



<b>EVERGREEN</b>	<b>TREES</b>

ITEM	COMMON NAME	BOTANICAL NAME	MATURE HEIGHT	MATURE WIDTH	SUN/SHADE	SIZE AND CONDITION	QTY
BRPL	BRISTLECONE PINE	E PINE PINUS ARISTATA		10'-20'	SUN/PART SHADE	6' HT, B&B	3
LPP	LODGEPOLE PINE	PINUS CONTORTA LATIFOLIA		10'-15'	SUN	6' HT, B&B	12
EMS	ENGLEMANN SPRUCE	PICEA ENGELMANNII	40'-60'	20'-30'	SUN	6' HT, B&B	1



<u>520,50000 0, 11,050</u>			MATURE	MATURE		OIZE AND	
ITEM	COMMON NAME	BOTANICAL NAME	MATURE HEIGHT	MATURE WIDTH	SUN/SHADE	SIZE AND CONDITION	QTY
MOSS	MOUNTAIN SNOWBERRY	TAIN SNOWBERRY SYMPHORICARPOS OREOPHILUS		2'-4'	SUN/PART SHADE	1 GAL CONT	44
ICR	ICEBERG ROSE	ROSA ICEBERG		18"-24"	SUN	5 GAL CONT	23
ALC	ALPINE CURRANT	RIBES ALPINUM	3-6'	3'-6"	SUN/PART SHADE	5 GAL CONT	5




<b>EVERG</b>	GREEN SHRUBS							
ITEM	COMMON NAME	BOTANICAL NAME MATURE MATURE HEIGHT WIDTH		SUN/SHADE	SIZE AND CONDITION	QTY		
СМЈ	COMMON JUNIPER	JUNIPERUS COMMUNIS	1-3'	3'-6"	SUN	5 GAL	26	



<u>ORNA</u>	MENTAL GRASSES						
ITEM	COMMON NAME	BOTANICAL NAME	MATURE HEIGHT	MATURE WIDTH	SUN/SHADE	SIZE AND CONDITION	QTY
BAM	BLONDE AMBITION GAMMA GRASS	BOUTELOUA GRACILLIS 'BLONDE AMBITION'	2-3'	20"-30"	SUN	1 GAL CONT	26



	PEREN	<u>INIALS</u>						
ITEM COMMON NAME		COMMON NAME	BOTANICAL NAME	MATURE HEIGHT	MATURE WIDTH	SUN/SHADE	SIZE AND CONDITION	QTY
	MOY	MOONSHINE YARROW	ACHILLEA 'MOONSHINE'	24-30"	18"-24"	SUN	4" POT/24" O.C.	23
	AJS	AUTUMN JOY STONECROP	SEDUM 'AUTUMN JOY'	18-24"	12"-18"	SUN	4" POT/24" O.C.	14



### Trees planted upon park land, public property, or within the Public Right of Way (PRW) are subject to the following restrictions

- An approved planting permit from the Office of the City Forester (OCF), regardless of approved plans, is required prior to planting. Administrative citations up to \$999 shall be issued for trees planted without an OCF issued permit..
- Only tree species approved by or listed on the OFC's approved street tree list shall be planted in the PRW.
- For a list of prohibited or suspended PRW trees, contact of visit the OCF website. If overhead utility wires exist in the PRW, only ornamental or trees maturing at 20 (twenty) feet maximum height shall be planted.
- Trees shall be centered in tree lawns and/or planting areas. Trees shall not be planted in tree lawns less than five feet wide unless authorized by the OCF.
- Where sidewalks are not present, trees shall be located as designated by Office of the City Forester. Planting in corner triangle formed by the first 30 (thirty) feet along the PRW in each direction from the corner is not permitted.
- Planting within 10 (ten) feet of alleys, driveways, or fire hydrants is not permitted.
- Planting within 20 (twenty) feet of stop signs is not permitted. Planting within 25 (twenty-five) feet of street lights is not permitted.
- Planting within five feet of water meters or pits is not permitted. • Large shade trees shall be spaced 35 (thirty-five) feet o.c. and ornamental trees 25 (twenty-five) feet o.c. or as designated by OCF.
- Trees shall be pruned to maintain a clearance of 13'-6" over streets and alleys and 6'-6" over remaining portions of PRW, including

Prior to digging, the Utility Notification Center of Colorado shall be contacted at 811 to locate underground utilities.

TREE PLANTING DETAIL - NOT TO SCALE

LANDSCAPE AREA					
ITEM	REQUIRED	PROVIDED			
TOTAL AREA: 54,313 SF					
DISTURBED LANDSCAPED AREA: 6,356 SF					
1 TREE / 1,500 SF (6,356 / 1,500)	5 TREES	4 DEC. + 1 EVG. TREES			
5 SHRUBS / 1,500 SF (6,356 / 1,500 x 25)	25 SHRUBS	20 DEC. + 5 EVG. SHRUBS			

LANDSCAPE BUF	FER						
LANDSCAPE BUFFER							
PROPERTY LINE	# PLANTS REQUIRED	# PLANTS PROVIDED					
SOUTH - 196 LF TYPE B	(4 DEC. TREES / 100 LF) = 8 DEC TREES	4 DEC. TREES					
	(4 EVG. TREES / 100 LF) = 8 EVG TREES	5 EVG. TREES					
	SHRUBS - 20	25 SHRUBS					
WEST - 92 LF TYPE B	(4 DEC. TREES / 100 LF) = 4 DEC TREES	0 DEC. TREES					
	(4 EVG. TREES / 100 LF) = 4 EVG TREES	4 EVG. TREES					
	SHRUBS - 10	10 SHRUBS					
NORTHWEST - 170 LF VASQUEZ CREEK TYPE B	(4 DEC. TREES / 100 LF) = 8 DEC TREES	8 DEC. TREES					
ITPEB	(4 EVG. TREES / 100 LF) = 8 EVG TREES	1 EVG. TREES					
	SHRUBS - 20	26 SHRUBS					
NORTH - 193 LF TYPE B	(4 DEC. TREES / 100 LF) = 8 DEC TREES	8 DEC. TREES					
	(4 EVG. TREES / 100 LF) = 8 EVG TREES	1 EVG. TREES					
	SHRUBS - 20	27 SHRUBS					
EAST - 93 LF TYPE B	(4 DEC. TREES / 100 LF) = 4 DEC TREES	8 DEC. TREES					
	(4 EVG. TREES / 100 LF) = 4 EVG TREES	3 EVG. TREES					
	SHRUBS - 10	24 SHRUBS					
SOUTHEAST - 192 LF TYPE B	(4 DEC. TREES / 100 LF) = 8 DEC TREES	10 DEC. TREES					
	(4 EVG. TREES / 100 LF) = 8 EVG TREES	3 EVG. TREES					
	SHRUBS - 20	25 SHRUBS					

### **GENERAL LANDSCAPE NOTES**

1. 1. ALL PLANTING BED AREAS SHALL BE MULCHED WITH 1-1/2" GRAY ROSE MULTI-COLORED RIVER ROCK, AT A DEPTH OF 3", INSTALLED OVER PERMEABLE WEED BARRIER FABRIC. DO NOT INSTALL EDGING BETWEEN WOOD MULCH AND ROCK MULCH AREAS.

2. SOD EDGER SHALL BE 14 GAUGE ROLLED TOP STEEL EDGING (DARK GREEN COLOR) IN THE LOCATIONS SHOWN ON THE PLANS. EDGER IS NOT REQUIRED WHERE SOD ABUTS CONCRETE.

3. ALL AREAS TO BE LANDSCAPED SHALL HAVE ORGANIC AMENDMENTS THOROUGHLY INCORPORATED INTO THE SOIL AT A RATE OF 5 CUBIC YARDS PER 1,000 SQUARE FEET, AND TILLED TO A DEPTH OF 6

4. ALL SOD AREAS, BED AREAS, AND LANDSCAPE AREAS SHALL BE FINE GRADED PRIOR TO INSTALLATION OF NEW PLANT MATERIAL. ROCKS, WOOD, AND ANY MATERIAL LARGER THAN 1" IN DIAMETER SHALL BE REMOVED FROM ALL PLANTING AREAS PRIOR TO SODDING AND PLANTING NEW MATERIALS.

5.EXISTING TURF, SHRUBS, TREES, AND PLANT MATERIAL TO BE REMOVED SHALL BE FULLY REMOVED FROM THE SITE, INCLUDING ALL ROOTS.

6. ALL LANDSCAPED AREAS SHALL BE WATERED BY A FULLY AUTOMATIC UNDERGROUND IRRIGATION SYSTEM. 7. SOD AREAS SHALL BE ZONED SEPARATELY THAN BEDS, AND SHALL BE IRRIGATED VIA POP-UP SPRAY HEADS PROVIDING FULL (HEAD TO HEAD) COVERAGE. HEADS SHALL BE COMMERCIAL GRADE WITH REPLACEABLE NOZZLES, PRESSURE REGULATORS, AND CHECK VALVES.

8.BED AREAS SHALL BE ZONED SEPARATELY THAN SOD AREAS, AND SHALL BE IRRIGATED BY INDIVIDUAL DRIP EMITTERS TO EACH PLANT. DRIP COMPONENTS SHALL BE COMMERCIAL GRADE RAIN-BIRD OR EQUAL POINT SOURCE EMITTERS, WITH ALL PLANTS RECEIVING IRRIGATION.



No.	Desc.	Date

MD Drawn By: Checked By:

ZONING SUBMITTAL

**ISSUE DATE** 08/12/2024

LANDSCAPE

## THE LANDING - TOWNHOMES MAJOR SITE PLAN

A PARCEL OF LAND BEING A PART OF THE NORTHWEST QUARTER (NW 1/4) OF SECTION 33, TOWNSHIP 1 SOUTH, RANGE 75 WEST OF THE 6TH PRINCIPAL MERIDIAN, TOWN OF WINTER PARK, COUNTY OF GRAND, STATE OF COLORADO

**185 VASQUEZ ROAD** 

ELECTRICAL LEGEND


SYMBOL	LOCATION	PRODUCT CODE	MOUNTING HEIGHT
04.01	04.01 WALL SCONCE M SERIES CYLINDERV01122024 - 12" DARK BRONZE 3000K		L1 7'-9"; L2 17'-3"; L3 28'-4"
04.02	04.02 GARAGE LIGHT ARC2 LED - P230KPEDDBXD		9'-6"
04.03	RECESSED CAN	ECO DOWNLIGHT LED 1" RECESSED - EDLM-NC-LDP	IN CEILING - 10'-4"
04.04	WALL SCONCE	ARCHER - BALLARD DESIGNS SKU#: LO459 - GUNMETAL	9'-7"


### **EXTERIOR LIGHTING CALCULATION VALUES**

BOUNDARY ILLUMINANCE (Fc)
AVERAGE = 1.2; MAXIMUM=7.9; MINIMUM=0.0; AVG/MIN=N.A.; MAX/MIN=N.A.

GROUND ILLUMINANCE (Fc)

AVERAGE = 1.12; MAXIMUM=6.8; MINIMUM=0.0; AVG/MIN=N.A.; MAX/MIN=N.A.








### **BASIS OF BEARINGS**

BASIS OF BEARINGS IS S41°45'47"W (ASSUMED) AS MEASURED ALONG THE SOUTHEAST FACING SUBJECT PROPERTY LINE AS EVIDENCED BY AN ALUMINUM CAP SITUATED AT THE NORTHERN END OF SAID LINE AND A PLASTIC CAP SITUATED AT THE SOUTHERN END OF SAID LINE AS DEPICTED HEREIN.

### CONSTRUCTION PLANS **FOR** THE LANDINGS

**185 VASQUEZ RD** WINTER PARK, COLORADO

A SUBDIVISION OF A PORTION OF THE NORTHWEST QUARTER (NW1/4) OF SECTION 33, TOWNSHIP 1 SOUTH, RANGE 75 WEST OF THE SIXTH PRINCIPAL MERIDIAN TOWN OF WINTER PARK, COUNTY OF GRAND, STATE OF COLORADO



**VICINITY MAP** 

C-1.0

C-1.1

C-2.2

C-3.0

C-3.1

C-3.2

C-4.0

C-4.1

C-5.0

C-5.1

C-5.3

1" = 250'

**COVER SHEET** 

DEMO PLAN

UTILITY PLAN

**DETAILS** 

**DETAILS** 

DETAILS

DETAILS

**DETAILS** 

SUPPLEMENTAL SHEETS

PARKING PLAN

ALTA SURVEY (EXISTING CONDITIONS)

UTILITY PROFILES

GENERAL NOTES

STORMWATER MANAGEMENT

EROSION CONTROL PLAN

OVERALL GRADING PLAN

DETAILED GRADING PLAN

DETAILED GRADING PLAN

### **TOWN OF WINTER PARK APPROVAL BLOCK**

THESE DESIGN, PLANS, AND CONTRACT DOCUMENTS ARE REVIEWED FOR CONCEPT AND GENERAL CONFORMANCE TO THE TOWN'S MINIMUM STANDARDS ONLY, AND THE PRIMARY RESPONSIBILITY FOR DESIGN ADEQUACY IS TO REMAIN WITH THE ENGINEER OF RECORDS. THE REVIEW DOES NOT IMPLY RESPONSIBILITY BY EITHER THE TOWN OF WINTER PARK OR THE TOWN ENGINEER FOR COMPLETENESS, ACCURACY OR CORRECTNESS OF CALCULATIONS. THE REVIEW DOES NOT IMPLY THAT QUANTITIES OF ITEMS INDICATED ON THE PLANS ARE THE FINAL QUANTITIES REQUIRED. THE REVIEW SHALL NOT BE CONSTRUED FOR ANY REASON AS ACCEPTANCE OF FINANCIAL RESPONSIBILITY BY THE TOWN OF WINTER PARK OR ANY OF THE REVIEWING PARTIES FOR ADDITIONAL ITEMS AND ADDITIONAL QUANTITIES OF ITEMS SHOWN THAT MAY BE REQUIRED DURING THE CONSTRUCTION PHASE.

APPROVED FOR CONSTRUCTION WITHIN ONE YEAR OF THE EARLIEST OF THESE DATES:

TOWN OF WINTER PARK	DATE	
TOWN ENGINEER	DATE	
EAST GRAND F.P.D. #4	DATE	

### **LEGEND**

PROPERTY LINE —— EXISTING FENCE EXISTING SANITARY SEWER EXISTING WATER MAIN EXISTING STORM DRAIN - EXISTING GAS MAIN EXISTING BURIED ELECTRIC —— EXISTING BURIED PHONE/CABLE —— 5230 —— PROPOSED CONTOUR --5230-- EXISTING CONTOUR PROPOSED SLOPE/FLOW ARROW

2.2% EXISTING SLOPE/FLOW ARROW

EXISTING SPOT ELEVATION EXISTING FLOWLINE SPOT ELEV X 5280.00 PROPOSED FINISHED GRADE ELEV

• 5280.00 PROPOSED FLOWLINE SPOT ELEV

FFE = FINISHED FLOOR ELEVATION

PROPOSED STORM DRAIN PIPE & ACCESSIBLE ENTRY

VEHICLE TRACKING CONTROL

SF SILT FENCE EROSION BARRIER

SEDIMENT LOG EROSION BARRIER

INLET PROTECTION EROSION BARRIER

ROCK SOCK

CONCRETE WASH OUT

STABILIZED STAGING AREA

### **AGENCY CONTACT LIST**

**ENGINEER:** CHAD FABRE

FABRE ENGINEERING, INC. 2063 PINON PLACE ERIE, CO 80516

SURVEYOR:

POWER SURVEYING 6911 BROADWAY DENVER, CO 80221 720-903-0048

303-702-1617

`8/5/24`

DING

Scale: AS NOTED **Date:** 8/5/24 Job No. WPTH-01

File No.

Sheet C-1.0

**ENGINEER'S CERTIFICATION** 

THESE CONSTRUCTION PLANS FOR THE LANDING TOWNHOMES PROJECT WERE PREPARED BY ME (OR UNDER MY DIRECT SUPERVISION) IN ACCORDANCE WITH THE REQUIREMENTS OF THE TOWN OF WINTER PARK STANDARDS AND SPECE CATIONS FOR DESIGN AND CONSTRUCTION.

CHAD C FABRE

8/5/24

DATE

### TOWN OF WINTER PARK GENERAL NOTES:

- 1. THE TOWN SIGNATURE AFFIXED TO THIS DOCUMENT INDICATES THE TOWN HAS REVIEWED THE DOCUMENT AND FOUND IT IN GENERAL CONFORMANCE WITH THE TOWN OF WINTER PARK STANDARDS AND SPECIFICATIONS FOR DESIGN AND CONSTRUCTION OR APPROVED VARIANCES TO THOSE REGULATIONS. THE TOWN, THROUGH ACCEPTANCE OF THIS DOCUMENT, ASSUMES NO RESPONSIBILITY, OTHER THAN STATED ABOVE, FOR THE COMPLETENESS AND/OR ACCURACY OF THESE DOCUMENTS. THE OWNER AND ENGINEER UNDERSTAND THAT THE RESPONSIBILITY FOR THE ENGINEERING ADEQUACY OF THE FACILITIES DEPICTED IN THIS DOCUMENT LIES SOLELY WITH THE
- LICENSED PROFESSIONAL ENGINEER WHOSE STAMP AND SIGNATURE IS AFFIXED TO THIS DOCUMENT. 2. ALL ROADWAY CONSTRUCTION SHALL CONFORM TO TOWN OF WINTER PARK STANDARDS AND
- SPECIFICATIONS FOR DESIGN AND CONSTRUCTION. 3. ALL MATERIALS AND WORKMANSHIP SHALL BE SUBJECT TO INSPECTION BY THE TOWN.THE TOWN RESERVES THE RIGHT TO ACCEPT OR REJECT ANY SUCH MATERIALS AND WORKMANSHIP THAT DOES NOT CONFORM TO ITS STANDARDS AND SPECIFICATIONS. THIS MAY RESULT IN A "STOP WORK ORDER" THAT WILL REMAIN IN EFFECT UNTIL APPROPRIATE CORRECTIONS ARE MADE TO THE SATISFACTION OF THE TOWN OF WINTER PARK.
- 4. THE CONTRACTOR PRIOR TO ACTUAL CONSTRUCTION SHALL VERIFY THE LOCATION OF EXISTING
- 5. THE CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS, BARRICADES, FLAGMEN, OR OTHER DEVICES NECESSARY TO PROVIDE FOR THE SAFETY IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
- 6. THE CONTRACTOR SHALL BE SOLELY AND COMPLETELY RESPONSIBLE FOR CONDITIONS AT AND ADJACENT TO THE JOB SITE, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY DURING PERFORMANCE OF THE WORK. THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS.
- 7. THE DUTY OF THE TOWN TO CONDUCT CONSTRUCTION INSPECTIONS AND REVIEW OF THE CONTRACTOR'S PERFORMANCE IS NOT INTENDED TO INCLUDE REVIEW OF THE CONTRACTOR'S SAFETY MEASURES IN, ON, OR NEAR THE CONSTRUCTION SITE.
- 8. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY THE OWNER/APPLICANT OF ANY PROBLEM IN CONFORMING TO THE APPROVED PLANS FOR ANY ELEMENT OF THE PROPOSED IMPROVEMENTS PRIOR TO ITS CONSTRUCTION.
- 9. IF CONSTRUCTION HAS NOT COMMENCED WITHIN TWO (2) YEARS OF APPROVAL, THE CONSTRUCTION PLANS MAY BE CONSIDERED INVALID. THESE PLANS MAY BE SUBJECT TO REREVIEW AND RE-APPROVAL BY THE TOWN.
- 10. PAVING SHALL NOT START UNTIL A SOILS REPORT AND PAVEMENT DESIGN IS ACCEPTED BY THE TOWN AND SUBGRADE COMPACTION TESTS ARE TAKEN AND ACCEPTED BY THE GEOTECHNICAL
- 11. IF DEWATERING IS USED TO INSTALL UTILITIES, CULVERTS, ETC., THEN A STATE CONSTRUCTION DEWATERING WASTEWATER DISCHARGE PERMIT IS REQUIRED FOR DISCHARGE INTO A STORM SEWER, CHANNEL IRRIGATION DITCH, OR ANY WATER OF THE UNITED STATES. A COPY OF THE PERMIT SHALL BE KEPT ON SITE AND FILED WITH THE TOWN PLANNING DEPARTMENT

### **GENERAL NOTES:**

- CONTRACTOR SHALL USE INDUSTRY ACCEPTED STANDARDS FOR THE CONSTRUCTION OF ROADWAY, UTILITIES AND EROSION CONTROL
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROMPTLY NOTIFYING THE ENGINEER OF ANY PROBLEMS OR POTENTIAL PROBLEMS IN CONFORMING TO THE DESIGN LINE AND GRADE FOR ANY ELEMENT OF THE CONSTRUCTION. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROMPTLY NOTIFYING THE ENGINEER OF SITE CONDITIONS THAT DIFFER FROM THOSE SHOWN ON THE APPROVED PLANS.
- 3. IN THE EVENT THE CONTRACTOR ALLOWS, AUTHORIZES, APPROVES OR CONSTRUCTS ITEMS THAT DIFFER FROM THE APPROVED PLANS, SPECIFICATIONS OR OTHER CONTRACT DOCUMENTS, WITHOUT WRITTEN APPROVAL BY THE ENGINEER, THE CONTRACTOR SHALL BE RESPONSIBLE FOR LIABILITY ARISING FROM SUCH CHANGES.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SAFEGUARDS, SAFETY DEVICES, PROTECTIVE EQUIPMENT, AND ANY OTHER NEEDED ACTION TO PROTECT THE LIFE, HEALTH AND SAFETY OF THE PUBLIC AND TO PROTECT PROPERTY IN CONNECTION WITH THE PERFORMANCE OF WORK COVERED BY THE CONTRACTOR.
- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING SAFE, PASSABLE ACCESS TO PRIVATE PROPERTIES ADJACENT TO THE WORK THROUGHOUT THE PERIOD OF CONSTRUCTION.
- 6. THE CONTRACTOR SHALL CONTACT THE UTILITY NOTIFICATION CENTER OF COLORADO FOR LOCATION OF UNDERGROUND GAS, ELECTRIC AND COMMUNICATION UTILITIES AT LEAST 48 HOURS PRIOR TO CONSTRUCTION (811). THE CONTRACTOR SHALL NOTIFY OTHER APPLICABLE UTILITY COMPANIES AS WELL TO OBTAIN FIELD LOCATES OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.
- 7. LOCATIONS OF UNDERGROUND UTILITIES AS SHOWN ON THE PLANS WERE TAKEN FROM THE RECORDS OF THE CONTROLLING AGENCIES OR FROM AGENCY MARKINGS IN THE FIELD. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THEIR COMPLETENESS OR ACCURACY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXISTENCE AND OR LOCATION OF ALL UNDERGROUND UTILITIES AND PARTICIPATE IN THE RESOLUTION OF ANY CONFLICTS PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF ALL NECESSARY UTILITY RELOCATIONS WITH THE APPROPRIATE UTILITY COMPANY.
- 9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE JOB SITE CONDITIONS THROUGHOUT THE DURATION OF CONSTRUCTION, INCLUDING SAFETY OF ALL PERSONS AND PROTECTION OF PROPERTY. THE REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED ONLY TO WORKING HOURS. THE CONTRACTOR SHALL DEFEND INDEMNIFY AND HOLD THE OWNER, THE ENGINEER AND THE GOVERNING JURISDICTION HARMLESS FOR ANY AND ALL LIABILITY, IN CONNECTION WITH THE PERFORMANCE OF WORK, EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER, THE ENGINEER OR THE GOVERNING JURISDICTION.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING NEARBY PUBLIC OR PRIVATE STREETS OF MUD AND DEBRIS, DUE TO CONSTRUCTION ACTIVITIES, ON A DAILY BASIS OR AS DIRECTED BY GOVERNING JURISDICTION PERSONNEL
- 11. THE CONTRACTOR SHALL HAVE IN HIS POSSESSION AT ALL TIMES THE APPROPRIATE EDITION OF THE GOVERNING JURISDICTION DESIGN AND CONSTRUCTION STANDARDS, ONE SET OF APPROVED CONSTRUCTION PLANS, THE STORM WATER MANAGEMENT PLAN, AND ALL REQUIRED PERMITS.
- 12. ALL CONSTRUCTION SHALL CONFORM TO INDUSTRY STANDARDS AS APPLICABLE TO ELEMENTS OF WORK NOT COVERED BY LOCAL AGENCY STANDARDS AND SPECIFICATIONS. REQUIREMENTS OF THE COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT, THE ENVIRONMENTAL PROTECTION AGENCY, THE FEDERAL EMERGENCY MANAGEMENT AGENCY, AND THE U.S. ARMY CORPS OF ENGINEERS, SHALL ALSO BE FOLLOWED AS THEY RELATE TO THE WORK.
- 13. THE CONTRACTOR SHALL OBTAIN, AT HIS EXPENSE, ALL PERMITS WHICH ARE NECESSARY TO
- PERFORM THE PROPOSED WORK. 14. ALL STATIONING IS ALONG THE CENTERLINE UNLESS OTHERWISE NOTED.
- 15. THE PROFILE GRADE ON THE PLANS IS THE CENTERLINE UNLESS OTHERWISE NOTED. 16. ALL WORKMANSHIP SHALL BE SUBJECT TO INSPECTION BY THE DEVELOPER, THE GOVERNING JURISDICTION, OR THEIR REPRESENTATIVES. ONE OR ALL OF THE PARTIES HAS THE RIGHT TO REJECT MATERIALS AND WORKMANSHIP WHICH DO NOT CONFORM TO SPECIFICATIONS.
- 17. THE CONTRACTOR SHALL NOTIFY REPRESENTATIVES FROM ALL GOVERNING JURISDICTIONS, AND THE PUBLIC UTILITY COMPANIES PRIOR TO PROCEEDING WITH ANY EXCAVATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING ANY EXISTING UTILITY (INCLUDING DEPTHS) WHICH MAY CONFLICT WITH THE PROPOSED CONSTRUCTION. ALL EXISTING UTILITIES SHALL BE PROTECTED FROM DAMAGE BY THE CONTRACTOR. DAMAGED UTILITIES SHALL BE REPAIRED BY THE CONTRACTOR AT HIS OWN EXPENSE. ALL ITEMS SHOWN ON THE PLANS AS EXISTING ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. THE ACTUAL LOCATIONS MAY VARY FROM THE PLANS, ESPECIALLY IN THE CASE OF UNDERGROUND UTILITIES. WHENEVER THE CONTRACTOR DISCOVERS A DISCREPANCY IN LOCATIONS, THE CONTRACTOR SHALL CONTACT THE ENGINEER IMMEDIATELY. ALL WORK PERFORMED IN THE AREA OF THE PUBLIC UTILITIES SHALL BE PERFORMED ACCORDING TO THE REQUIREMENTS OF THESE AGENCIES.
- 18. CONTRACTOR SHALL GIVE 72 HOUR NOTICE TO TOWN PERSONNEL TO PERFORM REQUIRED INSPECTIONS AND PRIOR TO ANY CONSTRUCTION ON THIS SITE.
- 19. LIMITS OF WORK: NO AREAS SHALL BE DISTURBED OUTSIDE OF THE TEMPORARY CONSTRUCTION EASEMENTS AND THE ROADWAY DISTURBANCE LIMITS.

### **ROADWAY CONSTRUCTION:**

- 1. CONTRACTOR SHALL ADHERE TO TOWN OF WINTER PARK STANDARDS SPECIFICATIONS FOR ROADWAY CONSTRUCTION WITH NO EXCEPTION, UNLESS APPROVED IN WRITING BY FABRE
- 2. LIFTS IN FILL AREAS SHALL NOT EXCEED 8 INCHES IN COMPACTED DEPTH. MAXIMUM SLOPES OF ALL CUTS & FILLS SHALL BE 3:1 UNLESS OTHERWISE NOTED. FILL SHALL NOT BE PLACED ON EXISTING TOPSOIL OR ORGANIC MATERIAL. TOPSOIL AND ORGANIC MATERIAL SHALL BE STRIPPED AND REMOVED FROM THE FILL AREA AND NOT USED IN THE FILL. FILL SHALL ONLY BE PLACED ON SUITABLE EXISTING SUBGRADE FREE OF ANY TOPSOIL AND/OR ORGANIC MATERIAL.
- 3. THE CONTRACTOR SHALL SAW-CUT ALL EXISTING PAVEMENT WHERE MATCH LINES WITH EXISTING EDGE OF PAVEMENT OCCUR.
- 4. PORTLAND CEMENT CONCRETE SHALL BE CONSTRUCTED IN ACCORDANCE WITH CDOT STANDARD
- ASPHALT PAVING SHALL BE IN ACCORDANCE WITH THE SOIL'S ENGINEER'S REPORT.
- 6. RETAINING WALL LOCATIONS AND HEIGHTS HAVE BEEN ESTABLISHED AS PART OF THESE PLANS. STRUCTURAL, GEOTECHNICAL, AND DRAINAGE ENGINEERING FOR THE WALLS IS BY OTHERS (SEE SEPARATE DESIGN DOCUMENT).

### **EROSION CONTROL**

- 1. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING AND DISPLAYING THE STORMWATER MANAGEMENT PERMIT. ADDITIONALLY A FIELD COPY OF THE STORMWATER MANAGEMENT PLAN SHALL BE LOCATED ON SITE AND MODIFIED AS FIELD CONDITIONS CHANGE.
- 2. AT ALL TIMES DURING CONSTRUCTION OF THIS PROJECT, EROSION CONTROL AND SEDIMENTATION CONTROL SHALL BE MAINTAINED TO PREVENT ERODED SOIL FROM LEAVING THE PROPERTY AND/OR DISTURBING WETLANDS.
- 3. ANY SETTLEMENT OR SOIL ACCUMULATIONS BEYOND THE PROPERTY LIMITS DUE TO GRADING OR EROSION SHALL BE REPAIRED IMMEDIATELY BY THE CONTRACTOR.
- 4. A WATER TRUCK SHALL BE UTILIZED DURING EARTHWORK OPERATIONS AS REQUIRED TO MINIMIZE DUST FROM EARTHWORK EQUIPMENT AND WIND.
- 5. A LAYER OF SUITABLE MULCH SHALL BE APPLIED TO ALL RE-SEEDED PORTIONS OF THE SITE WITHIN FOURTEEN DAYS OF THE COMPLETION OF RE-SEEDING. SAID MULCH SHALL BE APPLIED AT A RATE OF TWO TONS PER ACRE AND SHALL BE TACKED OR FASTENED BY AN APPROVED METHOD SUITABLE FOR THE TYPE OF MULCH USED.
- 6. SOILS THAT WILL BE STOCKPILED FOR MORE THAN THIRTY DAYS SHALL BE MULCHED AND SEEDED WITH A TEMPORARY OR PERMANENT GRASS COVER WITHIN FOURTEEN DAYS OF STOCKPILE CONSTRUCTION. IF STOCKPILES ARE LOCATED WITHIN 100 FEET OF A DRAINAGE WAY, ADDITIONAL SEDIMENT CONTROLS SUCH AS TEMPORARY DIKES OR SILT FENCES SHALL BE REQUIRED.
- 7. APPROVED EROSION AND SEDIMENT CONTROL "BEST MANAGEMENT PRACTICES" SHALL BE MAINTAINED AND KEPT IN GOOD REPAIR FOR THE DURATION OF THIS PROJECT. AT AT MINIMUM, THE CONTRACTOR OR HIS AGENT SHALL INSPECT ALL BMPs WEEKLY AND AFTER SIGNIFICANT PRECIPITATION EVENTS. ALL NECESSARY MAINTENANCE AND REPAIR SHALL BE COMPLETED IN A TIMELY MANNER. ACCUMULATED SEDIMENT OR DEBRIS ADVERSELY IMPACTS THE FUNCTIONING OF
- 8. THE CONTRACTOR MUST KEEP ALL POLLUTANTS, INCLUDING TRENCH BACKFILL MATERIALS, OIL, GREASE, ETC. FROM WASHING INTO THE STORM SEWER SYSTEM OR WATERWAYS.
- 9. THE OWNER, SITE DEVELOPER, CONTRACTOR, AND/OR THEIR AUTHORIZED AGENTS SHALL REMOVE ALL SEDIMENT, MUD, AND CONSTRUCTION DEBRIS THAT MAY ACCUMULATE IN THE DRAINAGE WAYS AND PUBLIC RIGHTS-OF-WAY AS A RESULT OF THIS SITE DEVELOPMENT. SAID REMOVAL SHALL BE CONDUCTED IN A TIMELY MANNER BY THE PROJECT OWNER.
- 10. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR REMEDIATION OF ANY ADVERSE IMPACTS TO ADJACENT WATERWAYS, WETLANDS, ETC. RESULTING FROM WORK DONE AS PART OF THIS PROJECT.
- 11. THE GENERAL CONTRACTOR, GRADING CONTRACTOR, AND/OR THEIR AUTHORIZED AGENTS SHALL ENSURE THAT ALL LOADS OF CUT AND FILL MATERIAL IMPORTED TO OR EXPORTED FROM THIS SITE SHALL BE PROPERLY COVERED TO PREVENT LOSS OF THE MATERIAL DURING TRANSPORT ON PUBLIC RIGHTS-OF WAY. THE PROJECT OWNER SHALL BE CONTACTED IF NECESSARY TO ENFORCE
- 12. THE USE OF REBAR, STEEL STAKES OR STEEL FENCE POSTS FOR STAKING DOWN STRAW OR HAY BALES OR TO SUPPORT SILT FENCING OR OTHER PERIMETER CONTROL DEVICES IS PROHIBITED.
- 13. THE EROSION CONTROL MEASURES MAY BE MODIFIED AS SITE CONDITIONS GOVERN. THIS MAY INCLUDE ELIMINATING CERTAIN EROSION CONTROL MEASURES IF THOSE MEASURES BECOME UNNECESSARY.
- 14. THE CLEANING OF CONCRETE DELIVERY TRUCK CHUTES INTO WATERWAYS IS PROHIBITED ON THE JOB SITE. THE DISCHARGE OF WATER CONTAINING WASTE CONCRETE TO THE STORM SEWER SYSTEM IS PROHIBITED.
- 15. THE EROSION CONTROL SYSTEM SHALL REMAIN OPERATIONAL UNTIL PAVING OF ROADWAYS IS COMPLETED AND VEGETATION IS RE-ESTABLISHED.
- 16. ANY DISTURBED AREAS WHICH ARE NOT TO BE LANDSCAPED OR CONSTRUCTED UPON SHALL BE MULCHED AND RE-SEEDED USING SEED MIXTURES AS SPECIFIED IN THE STORMWATER MANAGEMENT PLAN (SWMP).

### **DEEP UTILITIES:**

1. ALL MATERIALS AND WORKMANSHIP SHALL CONFORM TO GRAND COUNTY WATER & SANITATION DISTRICT #1 (GCWSD) STANDARDS.

### STORM SEWER NOTES:

- 1. LOCATION OF EXISTING STORM SEWER (INCLUDING CULVERTS) SHALL BE VERIFIED BY THE
- CONTRACTOR PRIOR TO START OF CONSTRUCTION. 2. STORM SEWER SHALL BE RCP IN ACCORDANCE WITH CDOT STANDARDS M-603-2.
- 3. ALL CULVERTS SHALL HAVE END SECTIONS ON BOTH THE UPSTREAM AND DOWNSTREAM ENDS OF THE PIPE UNLESS OTHERWISE NOTED ON THE PLANS.
- 4. STORM SEWER RCP SHALL HAVE BEDDING AND BACKFILL IN ACCORDANCE WITH CDOT STANDARD M-603-2 AND TOWN OF WINTER PARK STANDARDS.
- 5. PIPE LENGTHS FOR STORM SEWER ARE APPROXIMATE HORIZONTAL DISTANCES FROM END SECTION TO END SECTION. THEREFORE, DISTANCES SHOWN ON THE PLANS ARE APPROXIMATE ONLY AND COULD VARY. END SECTIONS ARE INCLUDED IN THE PIPE LENGTH SHOWN ON THE PLANS. FINAL LENGTH OF STORM SEWER SHALL BE SUFFICIENT TO PROVIDE THE ROAD SHOULDERS AND SIDE SLOPES TO NOT BE STEEPER THAN SHOWN ON THE TYPICAL ROAD SECTION.
- 6. DRIVEWAYS FOR ADJACENT PARCELS AND CULVERTS UNDER THE DRIVEWAYS SHALL BE DESIGNED IN THE FUTURE IN CONJUNCTION WITH DESIGNS FOR THE ADJACENT PARCELS.
- 7. RIPRAP TO BE ANGULAR.

### WATER MAIN NOTES:

- 1. ALL MATERIALS AND WORKMANSHIP SHALL BE IN CONFORMANCE WITH THE GRAND COUNTY WATER AND SANITATION DISTRICT #1 ENGINEERING AND CONSTRUCTION STANDARDS AND TOWN OF WINTER PARK STANDARDS AND/OR OTHER COVERNING AGENCIES. THE CONTRACTOR SHALL STRICTLY ADHERE TO THE DISTRICT'S STANDARDS AND DRAWINGS TO ASSURE THAT ALL FACILITIES ARE PROTECTED FROM DEEP
- 2. ALL WATER MAINS SHALL BE DUCTILE IRON PIPE CLASS 52 WATER PIPE WITH PUSH-ON SINGLE GASKET TYPE JOINTS (AWWA C111). ALL DUCTILE IRON PIPE SHALL BE WRAPPED WITH AN 8 MIL MINIMUM THICKNESS OF POLYETHYLENE MATERIAL PER AWWA STANDARD C105. VALVES SHALL BE RESILIENT SEAT
- 3. All FITTINGS SHALL BE MADE FROM GRAY-IRON OR DUCTILE IRON AND FURNISHED WITH MECHANICAL JOINT RESTRAINT. ALL FITTINGS SHALL HAVE A PRESSURE RATING OF 250 PSI AND SHALL BE WRAPPED WITH AN 8 MIL MINIMUM THICKNESS OF POLYETHYLENE MATERIAL PER AWWA STANDARD C105.
- 4. ALL FITTINGS SHALL BE RESTRAINED BY MECHANICAL JOINT RESTRAINT.
- 5. THERE SHALL BE A MINIMUM COVER OF 9 FEET OVER ALL WATER MAINS AND SERVICE LINES. 6. FIRE HYDRANTS SHALL BE MUELLER MOUNTAIN TYPE, OPEN LEFT, WITH DIRECTION OF OPENING CAST IN TOP OF HYDRANT. FIRE HYDRANT ASSEMBLIES SHALL INCLUDE ALL PIPE. FITTINGS, VALVES, VALVE BOXES, MATERIALS. AND LABOR WHICH ARE NECESSARY TO INSTALL THE HYDRANT COMPLETE IN PLACE. FIRE HYDRANT VALVES SHALL BE RESILIENT SEAT GATE VALVES-LEFT OPEN.
- 7. ALL BENDS, TEES, FIRE HYDRANT ASSEMBLIES, BLOW-OFFS AND PLUGS SHALL BE PROTECTED FROM THRUST BY USING CONCRETE THRUST BLOCKS.
- 8. THE EXISTING WATER MAINS AND THE EXISTING FIRE HYDRANTS SHALL REMAIN IN SERVICE DURING
- 9. ALL WORK COMPLETED WITHIN THE PUBLIC RIGHT-OF-WAY SHALL CONFORM TO THE REQUIREMENTS SET FORTH IN THE TOWN OF WINTER PARK STANDARDS OR OTHER GOVERNING AGENCY.
- 10. CHLORINATION TESTING, HYDROSTATIC TESTING AND FLUSHING OF MAINS SHALL BE PERFORMED IN ACCORDANCE WITH DISTRICT STANDARDS BY THE CONTRACTOR.
- 11. TRACER WIRE REQUIRED ON ALL WATER MAINS AND SERVICE LINES.

NOT TO SCALE

GRAND COUNTY WATER AND SANITATION DISTRICT #1 WATER MAIN NOTES

DATE: OCT 6, 2021

No: W-1

SANITARY SEWER NOTES:

- 1. ALL MATERIALS AND WORKMANSHIP SHALL BE IN CONFORMANCE WITH GRAND COUNTY WATER & SANITATION DISTRICT NO. 1 ENGINEERING CONSTRUCTION STANDARDS AND TOWN OF" WINTER PARK STANDARDS. THE CONTRACTOR SHALL STRICTLY ADHERE TO THE DISTRICT'S STANDARDS AND DRAWINGS TO ASSURE THAT ALL FACILITIES ARE PROTECTED FROM DEEP FROST PENETRATION.
- 2. ALL SEWER MAINS SHALL BE PVC, ASTM D-3034, SDR 35 OR APPROVED EQUAL.
- 3. SEWER LINES ABOVE OR LESS THAN 1.5 FEET BELOW A WATER MAIN SHALL BE ENCASED IN CONCRETE OR SHALL BE CONSTRUCTED WITH DUCTILE IRON PIPE FOR NINE TEN FEET EITHER SIDE OF THE WATER MAIN WITH NO JOINTS IN BETWEEN.
- 4. PIPE BEDDING SHALL BE DISTRICT STANDARD BEDDING.
- 5. ALL MANHOLES SHALL BE PRECAST AND SHALL HAVE SHAPED INVERTS. MANHOLE BASES SHALL BE PLACED ON 12" OF COMPACTED 1-1/2" CRUSHED ANGULAR ROCK BEDDING MATERIAL TO PREVENT
- 6. ALL SEWER MAINS SHALL SE TESTED IN ACCORDANCE WITH DISTRICT STANDARDS PRIOR TO ACCEPTANCE OR ANY CONNECTION TO AN EXISTING SEWER LINE.
- 7. SERVICE LINES INTO MANHOLES ARE NOT ACCEPTABLE, UNLESS APPROVED BY THE DISTRICT.
- 8. ALL WORK COMPLETED WITHIN THE PUBLIC RIGHT-OF-WAY SHALL CONFORM TO THE REQUIREMENTS SET FORTH IN THE TOWN OF WINTER PARK STANDARDS.


9. TRACER WIRE REQUIRED ON ALL WATER AND SANITATION SEWER MAINS AND SERVICE LINES.

NOT TO SCALE

AND SANITATION DISTRICT #1 SANITARY SEWER NOTES

DATE: OCT 6, 2021 No: S-1

GRAND COUNTY WATER



2

Scale: NONE

**Date:** 8/5/24 Job No. WPTH-01 File No.

Sheet C-1.1

CERTIFICATION	STABILIZED STORAGE AREAS
I HEREBY CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ENSURE THAT QUALIFIED PERSONNEL PROPERLY GATHER AND EVALUATE THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING IN THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FIN AND IMPRISONMENT FOR KNOWING VIOLATIONS.	G. NON-STORMWATER DISCHARGES. POTABLE WATER IS ANTICIPATED AS A NON-STORMWATER DISCHARGE. POTABLE WATER MAY BE USED FOR GRADING, DUST CONTROL, AND IRRIGATION OF EROSION CONTROL AND PERMANENT LANDSCAPING, CREATING RETURN FLOW. AN EFFORT SHALL BE MADE TO USE ONLY THE AMOUNT OF POTABLE WATER REQUIRED FOR THESE OPERATIONS. FLOWS FROM EMERGENCY FIRE FIGHTING ACTIVITIES AND UNCONTAMINATED SPRINGS MAY ALSO CONTRIBUTE TO NON-STORMWATER DISCHARGES.  DISCHARGE TO THE GROUND OF CONCRETE WASHOUT WATER FROM WASHING OF TOOLS AND CONCRETE MIXER CHUTES IS AN ANTICIPATED NON-STORMWATER DISCHARGE. THESE ACTIVITIES WILL BE
REPRESENTATIVE DATE	CARRIED OUT PER THE REQUIREMENTS DESCRIBED IN SECTION III.C.7(b)  DISCHARGE TO THE GROUND OF CONSTRUCTION DEWATERING MAY BE REQUIRED. LAND APPLICATION OF CONSTRUCTION WATER WILL BE AN ALLOWED NON-STORMWATER DISCHARGE AND MUST BE
THIS CERTIFICATION SHALL BE SIGNED UPON REQUEST FOR SUBMITTAL BY THE STATE OF COLORADO OR THE ENVIRONMENTAL PROTECTION AGENCY IN ACCORDANCE WITH THE FOLLOWING CRITERIA FROM THE GENERAL PERMIT SECTION I.F.1.	CARRIED OUT PER THE REQUIREMENTS DESCRIBED IN SECTION III.C.8.  H. OUTFALLS AND RECEIVING WATERS. DEVELOPED STORMWATER RUNOFF FROM THIS SITE WILL BE CONVEYED TO PROPOSED DETENTION BASINS OR DISCHARGED OFF THE SITE AS SHEET FLOW.
<ol> <li>IN THE CASE OF CORPORATIONS, BY A PRINCIPAL EXECUTIVE OFFICER OF AT LEAST THE LEVEL OF VICE—PRESIDENT OR HIS OR HER DULY AUTHORIZED REPRESENTATIVE, IF SUCH REPRESENTATIVE IS RESPONSIBLE FOR THE OVERALL OPERATION OF THE FACILITY FROM WHICH THE DISCHARGE DESCRIBED IN THE FORM ORIGINATES;</li> <li>IN THE CASE OF PARTNERSHIP, BY A GENERAL PARTNER;</li> <li>IN THE CASE OF A SOLE PROPRIETORSHIP, BY THE PROPRIETOR;</li> </ol>	THESE FLOWS WILL TRAVEL OVER THE SURFACE (E.G., STREETS AND SWALES). THE EXISTING DRAINAGE ULTIMATELY FLOWS INTO VASQUEZ CREEK, LOCATED WEST OF THE SITE.
4. IN THE CASE OF A MUNICIPAL, STATE, OR OTHER PUBLIC FACILITY, BY EITHER A PRINCIPAL EXECUTIVE OFFICER, RANKING ELECTED OFFICIAL, OR OTHER DULY AUTHORIZED EMPLOYEE.	SITE MAP  THE VICINITY MAP LOCATED ON THE COVER SHEET SHOWS THE DEVELOPMENT SITE. A DETAILED SITE PLAN WITH PROPOSED TEMPORARY AND PERMANENT BMPs IS PROVIDED ON SHEET C-2.1. THE
SUMMARY OF STORMWATER MANAGEMENT PLAN HIS STORMWATER MANAGEMENT PLAN (SWMP) COVERS CONSTRUCTION ACTIVITIES ASSOCIATED WITH THE LANDING TOWNHOMES. CONSTRUCTION ACTIVITIES WILL INVOLVE CLEARING AND GRUBBING	ONSITE SWMP FOLDER WILL CONTAIN THE UP-TO-DATE BMP MAP TO PROVIDE TRACKING OF PROGRESS. CONSTRUCTION SITE BOUNDARIES ARE INDICATED ON THESE DRAWINGS. (FOR THE CONSTRUCTION ACTIVITIES COVERED BY THE SWMP, THE PERMITTED AREA IS EQUIVALENT TO THE ARE INDICATED BY THE SITE PROPERTY BOUNDARIES.)
F THE SITE AS WELL AS GRADING ASSOCIATED WITH PROPOSED BUILDING SITES. THIS SWMP IDENTIFIES POTENTIAL SOURCES OF POLLUTION WHICH MAY REASONABLY BE EXPECTED TO AFFECT THE UALITY OF STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY, DESCRIBES THE PRACTICES TO BE USED TO REDUCE THE POLLUTANTS IN STORMWATER DISCHARGES ASSOCIATED ITH CONSTRUCTION ACTIVITY, AND ENSURES THE PRACTICES ARE SELECTED, INSTALLED, IMPLEMENTED, AND MAINTAINED IN ACCORDANCE WITH GOOD ENGINEERING PRACTICES.	STORMWATER MANAGEMENT CONTROLS
ROJECT LOCATION	A. SWMP ADMINISTRATOR. THE INDIVIDUAL(S), POSITION, OR TITLE THAT IS RESPONSIBLE FOR DEVELOPING, IMPLEMENTING, MAINTAINING, AND REVISING THE SWMP IS THE SWMP ADMINISTRATOR WILL SERVE AS THE COMPREHENSIVE POINT OF CONTACT FOR ALL ASPECTS IF THE FACILITY'S SWMP.
HIS PROJECT IS LOCATED IN; HE NORTHWEST 1/4 OF SECTION 33, DWNSHIP 1 SOUTH,	1. SWMP AMENDMENTS. THE SWMP ADMINISTRATOR SHALL AMEND THE SWMP: 1.1. WHEN THERE IS A CHANGE IN DESIGN, CONSTRUCTION, OPERATION, OR MAINTENANCE OF THE SITE, WHICH WOULD REQUIRE THE IMPLEMENTATION OF NEW OR REVISED BMPS; OR
NGE 75 WEST OF THE SIXTH PRINCIPAL MERIDIAN, WN OF WINTER PARK, UNITY OF GRAND,	<ul><li>1.2. IF THE SWMP PROVES TO BE INEFFECTIVE IN ACHIEVING THE GENERAL OBJECTIVES OF CONTROLLING POLLUTANTS IN STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY; OR</li><li>1.3. WHEN BMPS ARE NO LONGER NECESSARY AND ARE REMOVED.</li></ul>
TE OF COLORADO	SWMP CHANGES SHALL BE MADE PRIOR TO CHANGES IN THE SITE CONDITIONS, EXCEPT THOSE ADDRESSING BMP INSTALLATION AND/OR IMPLEMENTATION THAT ARE MADE RESPONSIVE TO CHANGIN CONDITIONS. WHEN CURRENT BMPS ARE DETERMINED INEFFECTIVE, CHANGES TO THE SWMP SHALL BE MADE AS SOON AS PRATICABLE, BUT IN NO CASE MORE THAN 72 HOURS AFTER THE
WNERS NAME AND ADDRESS AME] TREET ADDRESS]	CHANGES IN BMP INSTALLATION AND/OR IMPLEMENTATION OCCUR AT THE SITE.  THE SWMP ADMINISTRATOR MUST KEEP THE SWMP CURRENT BY REDLINING AND MARKING OTHER NOTES ON DRAWINGS AND IN THE TEXT OF THE SWMP TO ACCURATELY PORTRAY THE ACTUAL EROSION AND SEDIMENT CONTROLS USED ON THE SITE. NOTATION SHOULD SHOULD INCLUDE THE TIME AND DATE OF THE CHANGES IN THE FIELD. AND IDENTIFICATION OF THE BMPS REMOVED.
Y, STATE, ZIP CODE]	OR ADDED, AND THE LOCATION OF THOSE BMPS.  2. NOTICE OF TRANSFER, WHEN RESPONSIBILITY FOR STORMWATER DISCHARGES AT A CONSTRUCTION SITE CHANGES FROM ONE INDIVIDUAL TO ANOTHER, THE PERMITTEE SHALL SUBMIT A
ORMWATER MANAGEMENT ADMINISTRATOR	COMPLETED NOTICE OF TRANSFER AND ACCEPTANCE OF TERMS FORM. IF THE NEW RESPONSIBLE PARTY WILL NOT COMPLETE THE TRANSFER FORM, AND IF THE PERMITTEE HAS NO LEGAL RESPONSIBILITY, THROUGH OWNERSHIP OR CONTRACT, FOR THE CONSTRUCTION ACTIVITIES AT THE SITE, THE THE PERMIT MAY BE INACTIVATED UPON WRITTEN REQUEST TO THE DIVISION BY COMPLETION OF THE INACTIVATION NOTICE.  B. IDENTIFICATION OF POTENTIAL POLLUTANT SOURCES. SEE SECTION I.F.
ME (PRINTED)	C. BEST MANAGEMENT PRACTICES (BMPs) FOR STORMWATER POLLUTION PREVENTION. BMPs FOR STORMWATER POLLUTION PREVENTION INCLUDE STRUCTURAL AND NON-STRUCTURAL PRACTICES INTENDED TO REDUCE THE AMOUNT OF POLLUTANTS ENTERING STORMWATER RUNOFF AND LEAVING THE JOB SITE. ALL PERSONNEL RESPONSIBLE FOR IMPLEMENTATION AND MAINTENANCE OF
RESS	BMPs SHOULD REVIEW AND UNDERSTAND THE BMPs IDENTIFIED HEREIN AND ON THE PLAN.  FOUR BASIC APPROACHES USED FOR MITIGATING EROSION AND SEDIMENT LOSS FROM STORMWATER RUNOFF IN CONSTRUCTION AREAS ARE AS FOLLOWS:
ONE	- MINIMIZE ONSITE EROSION FROM OCCURRING AT THE OUTSET. INSTALL BMPS UP-GRADIENT OF SIGNIFICANT SURFACE DISTURBANCES TO REDUCE THE VOLUME AND VELOCITY OF RUN-ON ENTERING DISTURBED AREAS. STAGE CONSTRUCTION TO MINIMIZE THE AMOUNT OF TIME WHICH SOIL IS LEFT BARE. SURFACE ROUGHEN, TEMPORARILY SEED, AND MULCH AREAS WHEN PRACTICAL TO PROTECT OPEN DISTURBANCES. THESE PRACTICES HELP REDUCE THE AREA OF LAND SUSCEPTIBLE TO EROSION.
RMIT 5 PROJECT IS CERTIFIED TO DISCHARGE UNDER CDPS GENERAL PERMIT COR-03000 STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION, CERTIFICATION NUMBER COR THIS TIFICATION TO DISCHARGE AUTHORIZES, DURING CONSTRUCTION OF ROADWAYS, TO DISCHARGE STORMWATER FROM THE FACILITY IDENTIFIED AS THE VILLAGE TOWNHOMES, ON 1.19 TES DISTRIBUTES. CERTIFICATION IS EFFECTIVE ON AND EXPIRES ON THE ANTICIPATED CONSTRUCTION START DATE IS [MONTH] [YEAR] WITH FINAL STABILIZATION	<ul> <li>REDUCE SEDIMENT FROM STORMWATER RUNOFF. USE A COMBINATION OF TEMPORARY STRUCTURAL SEDIMENT CONTROLS TO MANAGE RUNOFF ONSITE SUCH AS ROCK SOCKS, SILT FENCE, AND INLET PROTECTION. THESE MEASURES ENCOURAGE SEDIMENT IN STORMWATER RUNOFF TO DEPOSIT AND ACCUMULATE, REDUCING THE TOTAL AMOUNT OF SEDIMENT IN RUNOFF.</li> <li>DETAIN STORMWATER RUNOFF FOR FREQUENTLY OCCURRING EVENTS. USE TEMPORARY SEDIMENT BASINS TO DETAIN RUNOFF, ENCOURAGE FURTHER SEDIMENTATION, AND PROTECT AGAINST DOWNSTREAM FLOODING.</li> <li>RELEASE STORMWATER RUNOFF IN A CONTROLLED MANNER. RISER PIPES IN TEMPORARY SEDIMENT BASINS WILL SLOWLY RELEASE STORMWATER AND REDUCE THE EROSION POTENTIAL OF</li> </ul>
CURING BY [MONTH] [YEAR].	DOWNSTREAM AREAS.  THE EROSION AND SEDIMENT CONTROL STRATEGY FOR A CONSTRUCTION PROJECT IS DYNAMIC. AS PHASES OF CONSTRUCTION PROGRESS, THE STRATEGY AND MEASURES IMPLEMENTED MUST
TE DESCRIPTION  CONSTRUCTION ACTIVITIES. THIS PROJECT WILL CONSIST OF SITE GRADING, UTILITY CONSTRUCTION OVER APPROXIMATELY 1.19 ACRES, WITH ASSOCIATED LANDSCAPING. SOIL DISTURBING ACTIVITIES WILL INCLUDE CLEARING AND GRUBBING; INSTALLING A STABILIZED CONSTRUCTION ENTRANCE, PERIMETER, AND OTHER EROSION AND SEDIMENT CONTROLS; DRIVE AISLE GRADING;	EVOLVE TO REMAIN EFFECTIVE.  1. STRUCTURAL PRACTICES FOR EROSION AND SEDIMENT CONTROL. STRUCTURAL BMPs ARE MEASURES TO REDUCE RUNOFF AND/OR REMOVE POLLUTANTS FROM RUNOFF. THOSE DESIGNATED FOF USE DURING CONSTRUCTION ACTIVITIES AND ARE TO BE REMOVED AFTER FINAL STABILIZATION ARE TEMPORARY MEASURES. THOSE DESIGNATED FOR USE AFTER CONSTRUCTION AS AN
AND PREPARATION FOR FINAL PLANTING AND SEEDING. CLEARING AND GRUBBING WILL BE NECESSARY TO ALLOW FOR GRADING AND UTILITY CONSTRUCTION. STORM CULVERTS WILL THEN FOLLOW. PERMANENT EROSION CONTROL WILL BE CONSTRUCTED ON THE SITE. CONSTRUCTION ACTIVITIES ASSOCIATES WITH THIS TYPE OF DEVELOPMENT TYPICALLY REQUIRE THE USE OF HEAVY EARTH MOVING EQUIPMENT, DUMP TRUCKS, GENERATORS, AND OTHER ASSORTED EQUIPMENT.  PROPOSED BMP SEQUENCE. THE GENERAL SEQUENCE OF BMP INSTALLATION WITH RESPECT TO CONSTRUCTION ACTIVITIES WILL BE AS FOLLOWS:	USE DURING CONSTRUCTION ACTIVITIES AND ARE TO BE REMOVED AFTER FINAL STABILIZATION ARE TEMPORARY MEASURES. THOSE DESIGNATED FOR USE AFTER CONSTRUCTION AS AN INTEGRAL PART OF THE FINAL STABILIZATION STRATEGY ARE PERMANENT MEASURES.  TEMPORARY STRUCTURAL BMPs IDENTIFIED FOR THIS SITE INCLUDE:  — TEMPORARY SEEDING  — SURFACE ROUGHENING
IASE I — PROJECT IMPLEMENTATION  APPOINT SWMP ADMINISTRATOR.	- MULCHING - MULCHING - SILT FENCE - VEHICLE TRACKING CONTROL
INSTALL/CONSTRUCT TEMPORARY OR PERMANENT EROSION CONTROL BMPs FROM AN APPROVED PLAN SET, INCLUDING: PERMANENT SEEDING, TEMPORARY SEEDING, SURFACE ROUGHENING, MULCHING, CONCRETE WASHOUT, SILT FENCE, VEHICLE TRACKING CONTROL, INLET PROTECTION, OUTLET PROTECTION, AND EROSION CONTROL MATTING.  GRADE THE CONSTRUCTION SITE FROM AND APPROVED PLAN SET, INCLUDING: DRIVE AISLES AND TURNAROUNDS. ETC.	- INLET PROTECTION - OUTLET PROTECTION - STRAW WATTLE
AREAS WHERE CONCRETE DRIVE AISLE INSTALLATION WILL NOT BEGIN IMMEDIATELY WILL BE TEMPORARILY RESEEDED AND SURFACE ROUGHENED. PHASES THAT ARE PROCEEDING WITH THE CONCRET DRIVE CONSTRUCTION SEQUENCE WILL NOT BE SEEDED AT THIS TIME BECAUSE THEY WILL BE ACTIVE CONSTRUCTION AREAS THAT WILL NOT BE DORMANT FOR MORE THAN 14 DAYS. MPLEMENT CONSTRUCTION SEQUENCE FOR CONCRETE DRIVE CONSTRUCTION:  STORM SEWER INSTALLATION, WITH CULVERT INLET PROTECTION INSTALLED AS STORM SEWER ARE INSTALLED.  PREPARATION OF ROAD SUB-GRADE.	PERMANENT STRUCTURAL BMPs IDENTIFIED FOR THIS SITE INCLUDE:  - EROSIONS CONTROL MATTING - WATER QUALITY BASINS - FLOW SPREADERS (FLAT RIPRAP PADS)
<ol> <li>CONSTRUCTION OF WATER, SANITARY SEWER, AND STORM SEWER AND STORM INLETS.</li> <li>PREPARATION OF ROAD SUB BASE.</li> <li>POURING OF CONCRETE DRIVE. ONCE DRIVE IS POURED, INLET PROTECTION WILL BE INSTALLED AROUND STORM INLETS.</li> </ol>	- PERMANENT SEEDING  LOCATIONS FOR EACH BMP ARE IDENTIFIED ON THE SWMP PLAN
6. INSTALLATION OF DRY UTILITIES (GAS, POWER, CABLE, PHONE) FOR LOTS.  CONSTRUCTION SEQUENCE WILL BE SCHEDULED TO ALLOW FOR NO LAPSE IN ACTIVITIES OF MORE THAN 14 DAYS. ONCE THIS SEQUENCE OF CONSTRUCTION ACTIVITIES HAS BEEN COMPLETED,	DISTURBED AREAS MUST BE PROPERLY MULCHED, OR SEEDED AND MULCHED, WITHIN 14 DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE NOT OTHERWISE PERMANENTLY STABILIZED. SOIL SURFACE STABILIZATION SHOULD ALSO BE APPLIED WITHIN 14 DAYS TO DISTURBED AREAS THAT MAY NOT BE AT FINAL GRADE BUT WILL REMAIN INACTIVE FOR MORE THAN
AREAS WHERE CONSTRUCTION WILL NO BEGIN WITHIN 14 DAYS WILL BE SURFACE ROUGHENED TO REDUCE EROSION POTENTIAL AND PROMOTE INFILTRATION AND WILL BE TEMPORARILY SEED IF THE WEATHER IS APPROPRIATE FOR SUCCESSFULLY SEED GERMINATION.	30 DAYS.  SOIL STOCKPILES AT THE SITE PERIMETER, OR WITHIN 100 FEET OF A DRAINAGEWAY, SHALL HAVE PERIMETER SEDIMENT CONTROLS INSTALLED AS SOON AS POSSIBLE. STOCKPILES EXPECTED TO BE
IMPLEMENT CONSTRUCTION ACTIVITIES RELATED TO THE CONSTRUCTION OF INDIVIDUAL HOMES INCLUDING DEBRIS MANAGEMENT, SPOIL PILE, AND SOIL STOCKPILES. INSTALL SPECIFIC BMPs AS SHOWN ON THE APPROVED PLAN SET AND IN ACCORDANCE WITH THE SWMP SHEETS, INCLUDED IN APPENDIX C, TO PROVIDE EROSION PROTECTION PRIOR TO LANDSCAPING AND RE-VEGETATION.	IN PLACE LONGER THAN 60 DAYS SHOULD BE TEMPORARILY SEEDED AND MULCHED WITHIN 14 DAYS AFTER STOCKPILE CONSTRUCTION.  2. NON-STRUCTURAL PRACTICES FOR EROSION AND SEDIMENT CONTROL. NON-STRUCTURAL BMPs ARE PRACTICES AIMED AT PREVENTING AND REDUCING THE AMOUNT OF POLLUTANTS FROM ENTERING RUNOFF, PRACTICES INCLUDE GOOD HOUSEKEEPING, MATERIALS HANDLING AND SPILL PREVENTION, AND WASTE MANAGEMENT AND DISPOSAL. PLEASE SEE SECTION III.C.4 FOR
COMPETE FINAL SITE GRADING INCLUDING REPLACING STOCKPILED TOPSOIL. IN ADDITION CLEAN OUT AND RE—GRADE (AS NECESSARY) DETENTION AND SEDIMENTATION PONDS USED FOR WATER QUALITY CAPTURE PURPOSES DURING CONSTRUCTION TO CONFORM TO THE DESIGN OF THE PERMANENT SITE DRAINAGE SYSTEM. FINAL (PERMANENT) SEEDING, SODDING, PLANTING, AND LANDSCAPING, OF THE SITE WILL BE THE RESPONSIBILITY OF THE DEVELOPER. SOME TEMPORARY STORMWATER CONTROLS, SUCH AS INLET PROTECTION FOR THE STORM SEWERS. SHOULD REMAIN IN PLACE DURING THIS PHASE.	MATERIALS HANDLING AND SPILL PREVENTION PRACTICES. PLEASE SEE SECTION III.C.7 FOR WASTE MANAGEMENT AND DISPOSAL PRACTICES.  GOOD HOUSEKEEPING. THE MOST EFFECTIVE FIRST STEPS TOWARDS PREVENTING POLLUTION IN STORMWATER FROM WORKSITES SIMPLY INVOLVE USING GOOD SENSE TO IMPROVE THE FACILITY'S
ICING OF CONSTRUCTION ACTIVITIES WILL PROGRESS AS RAPIDLY AS PRACTICAL TO MINIMIZE THE AMOUNT OF TIME THAT PORTIONS OF THE SITE ARE DISTURBED. AREAS THAT WILL BE	BASIC HOUSEKEEPING METHODS. POOR HOUSEKEEPING PRACTICES RESULT IN MORE WASTE BEING GENERATED THAN NECESSARY AND AN INCREASED POTENTIAL FOR STORMWATER CONTAMINATION WHERE A CLEAN AND ORDERLY WORKSITE REDUCES THE POSSIBILITY OF STORMWATER MIXING WITH POLLUTANTS. GOOD HOUSEKEEPING PRACTICES INCLUDE THE FOLLOWING:  — PREVENTATIVE MAINTENANCE OF EQUIPMENT
ACTIVE FOR MORE THAN 14 DAYS WILL BE SURFACE ROUGHENED TO REDUCE EROSION, SLOW RUNOFF VELOCITY, AND PROMOTE INFILTRATION. TEMPORARY SEEDING SHALL OCCUR ON ALL STURBED AREAS WHERE CONSTRUCTION ACTIVITIES ARE NOT COMPLETED WITHIN THE CALENDAR YEAR. INACTIVE AREAS WILL BE SEEDED WITH AN APPROVED TEMPORARY NATIVE SEED MIX HEN THE WEATHER CONDITIONS ARE SUCH THAT GROWTH OF NATIVE GRASSES FROM SEED IS POSSIBLE (SEE APPROVED EROSION CONTROL REPORT).	<ul> <li>PROPER MATERIALS STORAGE AND INVENTORY</li> <li>REGULAR CLEANUP SCHEDULES</li> <li>MAINTAINING WELL ORGANIZED WORK AREAS</li> </ul>
SE II - POST-CONSTRUCTION SITE INSPECTION	- PROPER SIGNAGE  3. PHASED BMP IMPLEMENTATION. EROSION AND SEDIMENT CONTROLS FOR CONSTRUCTION SHALL BE PHASED TO BE FULLY EFFECTIVE. A VEHICULAR TRACKING CONTROL DEVICE SHALL BE
OLLOWING COMPLETION OF THE PROJECT, INCLUDING FINAL RE-VEGETATION AND LANDSCAPING, THE SWMP ADMINISTRATOR WILL INSPECT AREAS THAT HAVE BEEN SEEDED AND LANDSCAPED TO ASSURE THAT THE RE-VEGETATION AND LANDSCAPING HAVE BEEN SUCCESSFUL IN ESTABLISHING UNIFORM GROUND COVER (70% OF PRE-DISTURBED COVER CRITERIA FOR RE-VEGETATION HAS NOT BEEN SUCCESSFUL, SPOT RE-VEGETATION OR OTHER REMEDIAL ACTIONS SHOULD BE IMPLEMENTED TO ASSURE COMPLIANCE WITH THE STORMWATER DISCHARGE PERMIT AND OTHER APPLICABLE REGULATIONS. THE SWMP ADMINISTRATOR WILL CARRY OUT THE INSPECTION.	INSTALLED PRIOR TO THE MOBILIZATION OF CONSTRUCTION EQUIPMENT ONSITE. PRIOR TO THE CLEARING AND GRUBBING OF THE CONSTRUCTION AREA, LOCALIZED CLEARING SHALL BE PERFORMED FOR THE PLACEMENT OF NECESSARY PERIMETER SEDIMENT CONTROL MEASURES (SILT FENCE, ETC.). SITE CLEARING SHALL COMMENCE ONLY AFTER PERIMETER EROSION CONTROL MEASURE ARE IN PLACE. PROPOSED SEDIMENT BASINS IN CUT AREAS SHALL BE CONSTRUCTED PRIOR TO GRADING OPERATIONS. THE PROPOSED DETENTION PONDS WILL BE CONSTRUCTED PRIOR TO THE CONSTRUCTION OF THE STORM SEWER SYSTEM. SEWER PROTECTION (I.E., INLET PROTECTION, CULVERT PROTECTION, OUTLET STRUCTURE PROTECTION) WILL BE INSTALLED AS EACH ELEMENT IS CONSTRUCTED AND ALSO WHENEVER SOIL EROSION FORM THE EXCAVATED MATERIAL HAS THE POTENTIAL FOR ENTERING A STORM DRAINAGE SYSTEM.
ITE AREA. THE PROPOSED SITE CONSISTS OF APPROXIMATELY 1.62 ACRES, MORE OR LESS. THE CURRENT PLAN IS TO DEVELOP THE LAND, IN ONE PHASE. THE TOTAL DISTURBED AREA IS .19 ACRES.	MATERIALS HANDLING AND SPILL PREVENTION. AREAS WHERE POTENTIAL SPILLS CAN OCCUR, E.G., STABILIZED STORAGE AREAS, SHALL HAVE THE FOLLOWING PREVENTION AND RESPONSE PROCEDURES IN PLACE.
SOILS. ACCORDING TO USDA NRCS CUSTOM SOIL RESOURCE WEBSITE, THE SITE CONSISTS OF THE FOLLOWING: 7.2% MAP UNIT SYMBOL NUMBER 31, FRISCO-PEELER GRAVELLY SANDY LOAMS ON 2-6 PERCENT SLOPES; 29.8% MAP UNIT SYMBOL NUMBER 32, FRISCO-PEELER GRAVELLY SAND LOAMS ON 6-25 PERCENT SLOPES; 15.9% MAP UNIT SYMBOL NUMBER 33, FRISCO-PEELER GRAVELLY SANDY LOAMS ON 25-65 PERCENT SLOPES: 47% MAP UNIT SYMBOL SYMBOL NUMBER 86, UINTA SANDY LOAM ON 2-15 PERCENT SLOPES. THE SITE CONSISTS OF 100%	4.1. MATERIALS HANDLING AND SPILL PREVENTION PRACTICES. MATERIALS USED AT CONSTRUCTION SITES CAN PRESENT A POTENTIAL FOR CONTAMINATION OF STORMWATER RUNOFF. THESE INCLUDE FUEL, OIL, LUBRICANTS, PAINTS, SOLVENTS, CONCRETE—CURING COMPOUNDS, AND OTHER LIQUID CHEMICALS SUCH AS FERTILIZERS, HERBICIDES, AND PESTICIDES. PRACTICES THAT CAN BE USED TO PREVENT OR MINIMIZE TOXIC MATERIALS IN RUNOFF FROM A CONSTRUCTION SITE ARE DESCRIBED IN THIS SECTION.
HYDROLOGIC SOIL GROUP TYPE B. SITE CURRENTLY HAS NOT BEEN DEVELOPED AND IS IN ITS HISTORIC CONDITION. CURRENTLY ANY STORMWATER DISCHARGE IS CARRYING POLLUTANTS AT A HISTORIC RATE.	A LIST OF ALL POTENTIALLY TOXIC OR HAZARDOUS CHEMICALS USED SHALL BE MAINTAINED IN THE SITE. WARNING LABELS MUST BE ATTACHED TO ALL POTENTIALLY TOXIC OR HAZARDOUS CHEMICALS. MATERIAL SAFETY DATA SHEETS (MSDS) AND OTHER SAFETY INFORMATION FOR A POTENTIALLY TOXIC OR HAZARDOUS SUBSTANCES WILL BE ON FILE AND ACCESSIBLE (ON THE SITE) DURING ALL PERIODS IN WHICH THE SUBSTANCE IS USED OR STORED.
EXISTING VEGETATION. A PORTION OF THE PROPERTY SLOPES AT 3% NORTHEAST TOWARDS VASQUEZ RD AND LIONS GATE DR AND THE OTHER PORTION SLOPES AT 10% EAST OWARDS VASQUEZ CREEK.  OTENTIAL POLITION SOURCES AT THE PROJECT SITE INCLUDE SEDIMENT FOUNDMENT (VEHICLE WASHING VEHICLE MAINTENANCE AND FLIFTING PAINT SOLVENTS WOOD TREATED PRODUCTS	IN ADDITION TO MAINTAINING AN INVENTORY OR POTENTIALLY TOXIC AND/OR HAZARDOUS MATERIALS AND ASSOCIATED SAFETY INFORMATION, THE FOLLOWING MATERIALS MANAGEMENT PRACTICES MUST BE FOLLOWED:  - MATERIALS WILL BE HANDLED IN ACCORDANCE WITH OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REQUIREMENTS AND MANUFACTURER'S INSTRUCTIONS.
OTENTIAL POLLUTION SOURCES AT THE PROJECT SITE INCLUDE SEDIMENT, EQUIPMENT/VEHICLE WASHING, VEHICLE MAINTENANCE AND FUELING, PAINT, SOLVENTS, WOOD TREATED PRODUCTS, SPHALT (BITUMINOUS) PAVING, CONCRETE, METAL, PETROLEUM PRODUCTS, WASTE STORAGE AND DISPOSAL, PORTABLE TOILETS, DUST OR PARTICULATE GENERATING PROCESSES, AND OFFSITE EDIMENT TRANSPORT FROM VEHICLE TRACKING, MANY CHEMICALS TYPICALLY ASSOCIATED WITH CONSTRUCTION ACTIVITIES ARE CONSTRUCTION ACTIVITIES AND EDITED AT THE STABLE FLORAGE AREA EXCEPT FOR SOILS STOCKPILE (S) MALOSE LOCATION(S) WILL BE NOTED ON THE SMALE BIAN THE BIAN THE SMALE BIAN THE	- CHEMICALS REGULATED UNDER THE COMPREHENSIVE ENVIRONMENTAL RESPONSE, COMPENSATIONS AND LIABILITY ACT (CERCLA) WILL BE REPORTED AND HANDLED IN ACCORDANCE WITH RELEVANT REGULATIONS MATERIALS STORED AT THE CONSTRUCTION SITE WILL BE COVERED OR OTHERWISE PROTECTED FROM THE ELEMENTS.
DIENTIAL POLLUTION SOURCES WILL BE AT THE STABILIZED STORAGE AREA, EXCEPT FOR SOILS STOCKPILE(S) WHOSE LOCATION(S) WILL BE NOTED ON THE SWMP PLAN. THE SWMP PLAN HALL BE CONTINUALLY UPDATED SHOULD THE STORAGE LOCATION(S) BE MOVED.	- THE QUANTITY OF FUEL AND LUBRICANTS STORED AT THE CONSTRUCTION SITE WILL BE LIMITED TO THE AMOUNT THAT IS RESPONSIBLE TO SUPPORT THE SPECIFIC CONSTRUCTION OR MAINTENANCE ACTIVITY. OFFSITE STORAGE OF FUEL, HYDRAULIC OIL, AND FORM OIL ARE PREFERABLE BULK STORAGE AREAS FOR MATERIALS NOT CONSUMED ON A DAILY BASIS ON A DAILY BASIS WILL BE ENCLOSED AND PROTECTED FROM THE ELEMENTS AND CONTAINED IN A MANNER TO
UL HANDLING, STORAGE, AND APPLICATION OF THESE MATERIALS REDUCE THE LIKELIHOOD THAT THESE CHEMICALS WILL CONTRIBUTE TO POLLUTION OF THE ENVIRONMENT. PREVENTATIVE ACTICES ARE DISCUSSED IN GREATER DETAIL IN THE MATERIALS HANDLING AND SPILL PREVENTION SECTION.  OLLOWING TABLE PROVIDES A BROAD LIST OF POTENTIAL POLLUTANTS FROM A RANGE OF CONSTRUCTION—RELATED ACTIVITIES. INCLUSION OF A CHEMICAL IN THE TABLE DOES NOT	PREVENT RELEASE TO THE ENVIRONMENT PETROLEUM PRODUCTS AND FERTILIZERS WILL BE STORED AT SEPARATE FACILITIES OR ISOLATED BY IMPERMEABLE BARRIERS HYPOCHLORITE AND OTHER CHLORINE COMPOUNDS WILL BE STORED SEPARATELY FROM OTHER MATERIALS AND KEPT DRY.
OLLOWING TABLE PROVIDES A BROAD LIST OF POTENTIAL POLLUTANTS FROM A RANGE OF CONSTRUCTION—RELATED ACTIVITIES. INCLUSION OF A CHEMICAL IN THE TABLE DOES NOT ECESSARILY IMPLY THAT THE CHEMICAL WILL BE USED AS A PART OF THE DEVELOPMENT CONSTRUCTION ACTIVITIES.  CALS POTENTIALLY ASSOCIATED WITH CONSTRUCTION ACTIVITIES	- AREAS AT THE CONSTRUCTION SITE THAT ARE USED FOR STORAGE OF TOXIC MATERIALS AND PETROLEUM PRODUCTS SHALL BE DESIGNED WITH AN ENCLOSURE, CONTAINER, OR DIKE LOCATED AROUND THE PERIMETER OF THE STORAGE AREA TO PREVENT DISCHARGE OF THESE MATERIALS IN RUNOFF FROM THE CONSTRUCTION SITE. THESE BARRIERS WILL ALSO FUNCTION TO CONTAIN SPILLED MATERIALS FROM CONTACT WITH SURFICE CONTACT BY STORAGE OF THE CONSTRUCTION OF THE CONSTRUCTION VEHICLES AND HEAVY FOUNDMENT SHALL BE CONSTRUCTION TO
TENTIAL POLLUTANT, SOURCES, AND LOCATION	<ul> <li>MEASURES TO PREVENT SPILLS OR LEAKS OF FUEL, GEAR OIL, LUBRICANTS, ANTIFREEZE, AND OTHER FLUIDS FROM CONSTRUCTION VEHICLES AND HEAVY EQUIPMENT SHALL BE CONSIDERED TO PROTECT GROUNDWATER AND RUNOFF QUALITY. ALL EQUIPMENT MAINTENANCE SHALL BE PERFORMED IN A DESIGNATED AREA AND MEASURES, SUCH AS DRIP PANS, SHALL BE USED TO CONTAIN PETROLEUM PRODUCTS, SPILLS OF CONSTRUCTION—RELATED MATERIALS, SUCH AS PAINTS, SOLVENTS, OR OTHER FLUIDS AND CHEMICALS, SHALL BE CLEANED UP IMMEDIATELY AND DISPOSED OR PROPERLY.</li> </ul>
LINE (BENZENE, TOLUENE, EHTYLBENZENE, XYLENE TETRAETHYL LEADS, METHYL TERTIARY BUTYL ETHER (MTBE), AND OTHER COMPOUNDS) TRUCTION VEHICLES, GAS CANS, AND GENERATORS	DISPOSED OR PROPERLY.  — CONCRETE TRUCKS AND OTHER CONCRETE COATED EQUIPMENT SHALL BE CLEANED ONLY IN DESIGNATED CONCRETE WASHOUT AREAS.  — HAZARDOUS MATERIALS AND WASTES SHALL BE STORED IN COVERED, LEAK—PROOF CONTAINERS.  — WHEN FUELING MUST TAKE PLACE ONSITE, DESIGNATE AN AREA AWAY FROM DRAINAGE COURSES TO BE USED. DEDICATED FUELING AREAS SHALL BE PROTECTED FROM STORMWATER RUN—ON
BILIZED STORAGE AREAS, ACCESS ROADS, ONSITE TANKS, AND FUEL SITES EL FUEL (AND ASSOCIATED CONSTITUENTS)	<ul> <li>WHEN FUELING MUST TAKE PLACE ONSITE, DESIGNATE AN AREA AWAY FROM DRAINAGE COURSES TO BE USED. DEDICATED FUELING AREAS SHALL BE PROTECTED FROM STORMWATER RUN-ON AND RUNOFF, AND SHALL BE A MINIMUM OF 50 FEET AWAY FROM DRAINAGE COURSES. THE AREA IS TO BE PROTECTED WITH SECONDARY CONTAINMENT SUCH AS BERMS AND DIKES. DROP CLOTHS OR DRAIN PANS CAN BE USED TO CATCH SPILLS IF NECESSARY. IF A SMALL SPILL DOES OCCUR, THE OPERATOR WILL USE ABSORBENT MATERIALS TO REMOVE AS MUCH OF THE SPIL AS POSSIBLE. THE SPENT ABSORBENT MATERIAL WILL BE DISPOSED OF PROPERLY AND PROMPTLY. THERE WILL BE NO BULK STORAGE OF FUEL ONSITE.</li> </ul>
TY CONSTRUCTION EQUIPMENT ILIZED STORAGE AREAS, ACCESS ROADS, FUEL SITE, STORAGE AREAS, AND LIFT HOUSES	- PORTABLE TOILETS WILL BE LOCATED AT LEAST 50 FEET AWAY FROM STORM SEWER INLETS. THEY WILL BE LOCATED IN LEVEL LOCATIONS, BUT NOT IN DRAINAGE PATHS, CURB AND GUTTER, OF ON SIDEWALKS OR DRIVES. THE SHALL ALSO BE STABILIZED TO MINIMIZE THE RISK OF TIPPING OVER. DOWNSTREAM PERIMETER CONTROLS SHALL BE INSTALLED TO PREVENT LEAKS FROM ENTERING THE STORM SEWER SYSTEM.
ÆNTS (TCE, TCA, AND OTHERS) LL CONTAINERS BILIZED STORAGE AREAS	4.2. SPILL CONTROL PRACTICES. ALL EMPLOYEES MUST BE TRAINED TO RECOGNIZE "SIGNIFICANT SPILLS" BASED ON THE RELATIVE TOXICITY OF THE MATERIAL. SPILLS SHOULD BE CLEANED IMMEDIATELY, USING AS LITTLE WATER AS POSSIBLE TO AVOID SPREADING. STOCKPILES OF CLEANUP MATERIALS SHOULD BE STORED IN AN EASILY ACCESSIBLE AREA. ALL EMPLOYEES
TS, STAINS, AND VARNISHES LL CONTAINERS, BULK CONTAINERS, AND SPRAY EQUIPMENT BILIZED STORAGE AREAS	SHOULD BE NOTIFIED OF THE LOCATION OF THE MSDS AND THE STORAGE LOCATION OF CLEANUP MATERIAL, AND SHOULD BE TRAINED TO CLEAN UP SPILLS. ALL CONSTRUCTION SITE PERSONNEL MUST FOLLOW SPILL PREVENTION AND CONTROL PRACTICES AS FOLLOWS:  — DESIGNATED INDIVIDUALS ON THE SITE WILL RECEIVE TRAINING ON CLEANUP PROCEDURES FOR VARIOUS TYPES OF CHEMICALS AND THE LOCATION OF INFORMATION AND CLEANUP SUPPLIES.
S AND WATERPROOFING COMPOUNDS L CONTAINERS AND BULK CONTAINERS	THE MSDS FOR A CHEMICAL PROVIDES INFORMATION ABOUT HEALTH HAZARDS, SAFE HANDLING, USE, AND CONTROL MEASURES. THE MSDS FOR ALL CHEMICALS USED ON THE SITE WILL BE KEPT ON THE SITE, AND WORKING WILL BE REQUIRED TO REVIEW THE MSDS FOR MATERIALS THEY ARE WORKING AROUND.  - SPILLS WILL BE CLEANED UP PROMPTLY AFTER DISCOVERY, AND MATERIALS USED FOR SPILL CLEANUP MUST BE DISPOSED OF OFFSITE AT AN APPROVED FACILITY.
LIZED STORAGE AREAS  LIZERS	- THE DESIGNATED COORDINATOR AND THE SWMP ADMINISTRATOR WILL BE NOTIFIED IMMEDIATELY OF ANY SPILL OF A TOXIC OR HAZARDOUS MATERIAL THAT THREATENS HOMAN HEALTH OR THE ENVIRONMENT. THE SWMP ADMINISTRATOR (OR DESIGNEE) MUST IN TURN REPORT THE SPILL TO THE APPROPRIATE FEDERAL, STATE, OR LOCAL AGENCIES IN ACCORDANCE WITH APPLICABLE REGULATIONS.
CONTAINERS BILIZED STORAGE AREAS	- IF A SPILL OCCURS, THIS PLAN WILL BE REVIEWED AND APPROPRIATELY REVISED TO INCORPORATE MEASURES TO REDUCE THE LIKELIHOOD OF A SPILL RECURRING AND TO IMPROVE RESPONS TIME AND CLEANUP EFFECTIVENESS.  - FOR ANY CONSTRUCTION ACTIVITIES COVERED BY THIS PLAN THAT INVOLVE THE USE OF TOXIC OR HAZARDOUS SUBSTANCES, ONSITE SPILL PREVENTION AND CLEANUP COORDINATION, IN THE EVENT OF A SPILL WILL BE THE RESPONSIBILITY OF THE SITE SUPERINTENDENT
RINE (HYPOCHLORITE) FECTIONS OF WATER LINE LIZED STORAGE AREAS, WATER LINE TESTING AREAS	EVENT OF A SPILL, WILL BE THE RESPONSIBILITY OF THE SITE SUPERINTENDENT.  5. DEDICATED CONCRETE OR ASPHALT BATCH PLANTS. THE USE OF A CONCRETE OR ASPHALT BATCH PLANTS ARE NOT ANTICIPATED; ITS USE WILL NOT BE PERMITTED UNDER THIS APPLICATIONS.
IT CONTAINERS	6. VEHICLE TRACKING CONTROL. PRACTICES IMPLEMENTED AT THE SITE TO CONTROL POTENTIAL SEDIMENT DISCHARGES FROM VEHICLE TRACKING INCLUDE:  - VEHICLE TRACKING CONTROL (VTC)  - MINIMIZING SITE ACCESS
ILIZED STORAGE AREAS, CONCRETE WASHOUT AREAS  ALS, PAINT CHIPS, WOOD CHIPS, INSULATION, ASBESTOS, AND PLASTICS	<ul> <li>MINIMIZING SITE ACCESS</li> <li>GRAVELED PARKING AREAS</li> <li>VEHICLE ACCESS TO THE SITE WILL BE MINIMIZED THROUGH THE USE OF CONSTRUCTION AND SILT FENCE. ACCESS WILL ONLY BE ALLOWED AT THE ENTRANCES FROM VASQUEZ RD. WHERE VEHICLE</li> </ul>
STRUCTION DEBRIS BILLIZED STORAGE AREAS, ACCESS ROADS  ORIGINATION OF THE PROPERTY OF THE PROP	VEHICLE ACCESS TO THE SITE WILL BE MINIMIZED THROUGH THE USE OF CONSTRUCTION AND SILT FENCE. ACCESS WILL ONLY BE ALLOWED AT THE ENTRANCES FROM VASQUEZ RD. WHERE VEHICLE TRACKING CONTROL (VTC) WILL BE INSTALLED. A VTC WILL BE PROVIDED AT THE CONSTRUCTION TRAILERS ARE ESTABLISHED ON LOTS BY PRODUCTION STAFF DURING THE COURSE OF HOME CONSTRUCTION, A VTC WILL BE PROVIDED.
OBIOLOGICAL CONTAMINANTS (COLIFORM, GIARDIA, ETC.) TARY WASTEWATER TIC TANK/LEACH FIELD SYSTEMS, BROKEN SEWER LINES, PORTABLE TOILETS	STREETS WILL BE SCRAPED, SWEPT, OR BOTH, AND GUTTERS WILL BE CLEANED AS NECESSARY AND FOLLOWING:  — COMPLETION OF FOUNDATION EXCAVATION AND BACKFILLING,  — COMPLETION OF WATER AND SEWER CONNECTION, OR
COL ISTRUCTION VEHICLES AND EQUIPMENT, SMALL CONTAINERS, AND BULK CONTAINERS BILIZED STORAGE AREAS. ACCESS ROADS. AND COMPRESSOR SITE	- COMPLETION OF FLAT WORK  PARKING FOR PRODUCTION STAFF AND SUB-CONTRACTORS WILL BE ALLOWED ONLY ON PAVED OR OTHERWISE STABILIZED AREAS. DURING WET WEATHER, VEHICLE ACCESS TO LOTS WILL BE
ABILIZED STORAGE AREAS, ACCESS ROADS, AND COMPRESSOR SITE  CKIFIERS  LK CONTAINERS AND SPRAY EQUIPMENT	MINIMIZED TO THE EXTENT PRACTICAL. 7. WASTE MANAGEMENT AND DISPOSAL. THE SITE SHALL IMPLEMENT BMP'S TO CONTROL STORMWATER POLLUTION FROM SITE WASTES SUCH AS BUILDING WASTER (LIQUID AND SOLID) AND

IZED STORAGE AREAS -STORMWATER DISCHARGES. POTABLE WATER IS ANTICIPATED AS A NON-STORMWATER DISCHARGE. POTABLE WATER MAY BE USED FOR GRADING, DUST CONTROL, AND IRRIGATION OF OSION CONTROL AND PERMANENT LANDSCAPING, CREATING RETURN FLOW. AN EFFORT SHALL BE MADE TO USE ONLY THE AMOUNT OF POTABLE WATER REQUIRED FOR THESE OPERATIONS.

OWS FROM EMERGENCY FIRE FIGHTING ACTIVITIES AND UNCONTAMINATED SPRINGS MAY ALSO CONTRIBUTE TO NON-STORMWATER DISCHARGES. RGE TO THE GROUND OF CONCRETE WASHOUT WATER FROM WASHING OF TOOLS AND CONCRETE MIXER CHUTES IS AN ANTICIPATED NON-STORMWATER DISCHARGE. THESE ACTIVITIES WILL BE RRIED OUT PER THE REQUIREMENTS DESCRIBED IN SECTION III.C.7(b) ARGE TO THE GROUND OF CONSTRUCTION DEWATERING MAY BE REQUIRED. LAND APPLICATION OF CONSTRUCTION WATER WILL BE AN ALLOWED NON-STORMWATER DISCHARGE AND MUST BE ARRIED OUT PER THE REQUIREMENTS DESCRIBED IN SECTION III.C.8. DUTFALLS AND RECEIVING WATERS. DEVELOPED STORMWATER RUNOFF FROM THIS SITE WILL BE CONVEYED TO PROPOSED DETENTION BASINS OR DISCHARGED OFF THE SITE AS SHEET FLOW. THESE FLOWS WILL TRAVEL OVER THE SURFACE (E.G., STREETS AND SWALES). THE EXISTING DRAINAGE ULTIMATELY FLOWS INTO VASQUEZ CREEK, LOCATED WEST OF THE SITE. CINITY MAP LOCATED ON THE COVER SHEET SHOWS THE DEVELOPMENT SITE. A DETAILED SITE PLAN WITH PROPOSED TEMPORARY AND PERMANENT BMPs IS PROVIDED ON SHEET C-2.1. THE SITE SWMP FOLDER WILL CONTAIN THE UP-TO-DATE BMP MAP TO PROVIDE TRACKING OF PROGRESS. CONSTRUCTION SITE BOUNDARIES ARE INDICATED ON THESE DRAWINGS. (FOR THE NSTRUCTION ACTIVITIES COVERED BY THE SWMP, THE PERMITTED AREA IS EQUIVALENT TO THE ARE INDICATED BY THE SITE PROPERTY BOUNDARIES.) RMWATER MANAGEMENT CONTROLS WMP ADMINISTRATOR. THE INDIVIDUAL(S), POSITION, OR TITLE THAT IS RESPONSIBLE FOR DEVELOPING, IMPLEMENTING, MAINTAINING, AND REVISING THE SWMP IS \_\_\_\_\_\_. THE SWMP DMINISTRATOR WILL SERVE AS THE COMPREHENSIVE POINT OF CONTACT FOR ALL ASPECTS IF THE FACILITY'S SWMP. WMP AMENDMENTS. THE SWMP ADMINISTRATOR SHALL AMEND THE SWMP:
WHEN THERE IS A CHANGE IN DESIGN, CONSTRUCTION, OPERATION, OR MAINTENANCE OF THE SITE, WHICH WOULD REQUIRE THE IMPLEMENTATION OF NEW OR REVISED BMPS; OR IF THE SWMP PROVES TO BE INEFFECTIVE IN ACHIEVING THE GENERAL OBJECTIVES OF CONTROLLING POLLUTANTS IN STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY; WHEN BMPS ARE NO LONGER NECESSARY AND ARE REMOVED. CHANGES SHALL BE MADE PRIOR TO CHANGES IN THE SITE CONDITIONS, EXCEPT THOSE ADDRESSING BMP INSTALLATION AND/OR IMPLEMENTATION THAT ARE MADE RESPONSIVE TO CHANGING IDITIONS. WHEN CURRENT BMPS ARE DETERMINED INEFFECTIVE, CHANGES TO THE SWMP SHALL BE MADE AS SOON AS PRATICABLE, BUT IN NO CASE MORE THAN 72 HOURS AFTER THE FINAL STABILIZATION PRACTICES FOR OBTAINING A VEGETATIVE COVER SHOULD INCLUDE USING AN APPROVED SEED MIX. SOME TEMPORARY STORMWATER CONTROLS, SUCH ASS INLET PROTECTION, MP ADMINISTRATOR MUST KEEP THE SWMP CURRENT BY REDLINING AND MARKING OTHER NOTES ON DRAWINGS AND IN THE TEXT OF THE SWMP TO ACCURATELY PORTRAY THE ACTUAL OSION AND SEDIMENT CONTROLS USED ON THE SITE. NOTATION SHOULD SHOULD INCLUDE THE TIME AND DATE OF THE CHANGES IN THE FIELD, AND IDENTIFICATION OF THE BMPS REMOVED IOTICE OF TRANSFER. WHEN RESPONSIBILITY FOR STORMWATER DISCHARGES AT A CONSTRUCTION SITE CHANGES FROM ONE INDIVIDUAL TO ANOTHER, THE PERMITTEE SHALL SUBMIT A COMPLETED NOTICE OF TRANSFER AND ACCEPTANCE OF TERMS FORM. IF THE NEW RESPONSIBLE PARTY WILL NOT COMPLETE THE TRANSFER FORM, AND IF THE PERMITTEE HAS NO LEGAL SIBILITY, THROUGH OWNERSHIP OR CONTRACT, FOR THE CONSTRUCTION ACTIVITIES AT THE SITE, THE THE PERMIT MAY BE INACTIVATED UPON WRITTEN REQUEST TO THE DIVISION BY OMPLETION OF THE INACTIVATION NOTICE. ENTIFICATION OF POTENTIAL POLLUTANT SOURCES. SEE SECTION I.F. EST MANAGEMENT PRACTICES (BMPs) FOR STORMWATER POLLUTION PREVENTION. BMPs FOR STORMWATER POLLUTION PREVENTION INCLUDE STRUCTURAL AND NON-STRUCTURAL PRACTICES TENDED TO REDUCE THE AMOUNT OF POLLUTANTS ENTERING STORMWATER RUNOFF AND LEAVING THE JOB SITE. ALL PERSONNEL RESPONSIBLE FOR IMPLEMENTATION AND MAINTENANCE OF ASIC APPROACHES USED FOR MITIGATING EROSION AND SEDIMENT LOSS FROM STORMWATER RUNOFF IN CONSTRUCTION AREAS ARE AS FOLLOWS: INIMIZE ONSITE EROSION FROM OCCURRING AT THE OUTSET. INSTALL BMPS UP-GRADIENT OF SIGNIFICANT SURFACE DISTURBANCES TO REDUCE THE VOLUME AND VELOCITY OF RUN-ON NTERING DISTURBED AREAS. STAGE CONSTRUCTION TO MINIMIZE THE AMOUNT OF TIME WHICH SOIL IS LEFT BARE. SURFACE ROUGHEN, TEMPORARILY SEED, AND MULCH AREAS WHEN DUCE SEDIMENT FROM STORMWATER RUNOFF. USE A COMBINATION OF TEMPORARY STRUCTURAL SEDIMENT CONTROLS TO MANAGE RUNOFF ONSITE SUCH AS ROCK SOCKS, SILT FENCE, AND LET PROTECTION. THESE MEASURES ENCOURAGE SEDIMENT IN STORMWATER RUNOFF TO DEPOSIT AND ACCUMULATE, REDUCING THE TOTAL AMOUNT OF SEDIMENT IN RUNOFF. TAIN STORMWATER RUNOFF FOR FREQUENTLY OCCURRING EVENTS. USE TEMPORARY SEDIMENT BASINS TO DETAIN RUNOFF, ENCOURAGE FURTHER SEDIMENTATION, AND PROTECT AGAINST OWNSTREAM FLOODING. LEASE STORMWATER RUNOFF IN A CONTROLLED MANNER. RISER PIPES IN TEMPORARY SEDIMENT BASINS WILL SLOWLY RELEASE STORMWATER AND REDUCE THE EROSION POTENTIAL OF ROSION AND SEDIMENT CONTROL STRATEGY FOR A CONSTRUCTION PROJECT IS DYNAMIC. AS PHASES OF CONSTRUCTION PROGRESS, THE STRATEGY AND MEASURES IMPLEMENTED MUST RUCTURAL PRACTICES FOR EROSION AND SEDIMENT CONTROL. STRUCTURAL BMPs ARE MEASURES TO REDUCE RUNOFF AND/OR REMOVE POLLUTANTS FROM RUNOFF. THOSE DESIGNATED FOR E DURING CONSTRUCTION ACTIVITIES AND ARE TO BE REMOVED AFTER FINAL STABILIZATION ARE TEMPORARY MEASURES. THOSE DESIGNATED FOR USE AFTER CONSTRUCTION AS AN ITEGRAL PART OF THE FINAL STABILIZATION STRATEGY ARE PERMANENT MEASURES. RARY STRUCTURAL BMPs IDENTIFIED FOR THIS SITE INCLUDE: EMPORARY SEEDING IRFACE ROUGHENING HICLE TRACKING CONTROL LET PROTECTION JTLET PROTECTION NENT STRUCTURAL BMPs IDENTIFIED FOR THIS SITE INCLUDE: IONS CONTROL MATTING ATER QUALITY BASINS LOW SPREADERS (FLAT RIPRAP PADS) RMANENT SEEDING ONS FOR EACH BMP ARE IDENTIFIED ON THE SWMP PLAN BED AREAS MUST BE PROPERLY MULCHED, OR SEEDED AND MULCHED, WITHIN 14 DAYS AFTER FINAL GRADE IS REACHED ON ANY PORTION OF THE SITE NOT OTHERWISE PERMANENTL' ABILIZED. SOIL SURFACE STABILIZATION SHOULD ALSO BE APPLIED WITHIN 14 DAYS TO DISTURBED AREAS THAT MAY NOT BE AT FINAL GRADE BUT WILL REMAIN INACTIVE FOR MORE THAN TOCKPILES AT THE SITE PERIMETER, OR WITHIN 100 FEET OF A DRAINAGEWAY, SHALL HAVE PERIMETER SEDIMENT CONTROLS INSTALLED AS SOON AS POSSIBLE. STOCKPILES EXPECTED TO BE PLACE LONGER THAN 60 DAYS SHOULD BE TEMPORARILY SEEDED AND MULCHED WITHIN 14 DAYS AFTER STOCKPILE CONSTRUCTION. ON-STRUCTURAL PRACTICES FOR EROSION AND SEDIMENT CONTROL. NON-STRUCTURAL BMPs ARE PRACTICES AIMED AT PREVENTING AND REDUCING THE AMOUNT OF POLLUTANTS FROM NTERING RUNOFF, PRACTICES INCLUDE GOOD HOUSEKEPING, MATERIALS HANDLING AND SPILL PREVENTION, AND WASTE MANAGEMENT AND DISPOSAL. PLEASE SEE SECTION III.C.4 FOR ATERIALS HANDLING AND SPILL PREVENTION PRACTICES. PLEASE SEE SECTION III.C.7 FOR WASTE MANAGEMENT AND DISPOSAL PRACTICES. SIC HOUSEKEEPING METHODS. POOR HOUSEKEEPING PRACTICES RESULT IN MORE WASTE BEING GENERATED THAN NECESSARY AND AN INCREASED POTENTIAL FOR STORMWATER FAMINATION WHERE A CLEAN AND ORDERLY WORKSITE REDUCES THE POSSIBILITY OF STORMWATER MIXING WITH POLLUTANTS. GOOD HOUSEKEEPING PRACTICES INCLUDE THE FOLLOWING: ROPER MATERIALS STORAGE AND INVENTORY GULAR CLEANUP SCHEDULES INTAINING WELL ORGANIZED WORK AREAS ROPER SIGNAGE PHASED BMP IMPLEMENTATION. EROSION AND SEDIMENT CONTROLS FOR CONSTRUCTION SHALL BE PHASED TO BE FULLY EFFECTIVE. A VEHICULAR TRACKING CONTROL DEVICE SHALL BE NSTALLED PRIOR TO THE MOBILIZATION OF CONSTRUCTION EQUIPMENT ONSITE. PRIOR TO THE CLEARING AND GRUBBING OF THE CONSTRUCTION AREA, LOCALIZED CLEARING SHALL BE RFORMED FOR THE PLACEMENT OF NECESSARY PERIMETER SEDIMENT CONTROL MEASURES (SILT FENCE, ETC.). SITE CLEARING SHALL COMMENCE ONLY AFTER PERIMETER EROSION CONTROL EASURE ARE IN PLACE, PROPOSED SEDIMENT BASINS IN CUT AREAS SHALL BE CONSTRUCTED PRIOR TO GRADING OPERATIONS. THE PROPOSED DETENTION PONDS WILL BE CONSTRUCTED RIOR TO THE CONSTRUCTION OF THE STORM SEWER SYSTEM. STORM SEWER PROTECTION (I.E., INLET PROTECTION, CULVERT PROTECTION, OUTLET STRUCTURE PROTECTION) WILL BE INSTALLED S EACH ELEMENT IS CONSTRUCTED AND ALSO WHENEVER SOIL EROSION FORM THE EXCAVATED MATERIAL HAS THE POTENTIAL FOR ENTERING A STORM DRAINAGE SYSTEM. ATERIALS HANDLING AND SPILL PREVENTION. AREAS WHERE POTENTIAL SPILLS CAN OCCUR, E.G., STABILIZED STORAGE AREAS, SHALL HAVE THE FOLLOWING PREVENTION AND RESPONSE ROCEDURES IN PLACE. MATERIALS HANDLING AND SPILL PREVENTION PRACTICES. MATERIALS USED AT CONSTRUCTION SITES CAN PRESENT A POTENTIAL FOR CONTAMINATION OF STORMWATER RUNOFF. THESE INCLUDE FUEL, OIL, LUBRICANTS, PAINTS, SOLVENTS, CONCRETE-CURING COMPOUNDS, AND OTHER LIQUID CHEMICALS SUCH AS FERTILIZERS, HERBICIDES, AND PESTICIDES. PRACTICES THAT CAN BE USED TO PREVENT OR MINIMIZE TOXIC MATERIALS IN RUNOFF FROM A CONSTRUCTION SITE ARE DESCRIBED IN THIS SECTION. OF ALL POTENTIALLY TOXIC OR HAZARDOUS CHEMICALS USED SHALL BE MAINTAINED IN THE SITE. WARNING LABELS MUST BE ATTACHED TO ALL POTENTIALLY TOXIC OR HAZARDOUS EMICALS. MATERIAL SAFETY DATA SHEETS (MSDS) AND OTHER SAFETY INFORMATION FOR A POTENTIALLY TOXIC OR HAZARDOUS SUBSTANCES WILL BE ON FILE AND ACCESSIBLE (ON THE E) DURING ALL PERIODS IN WHICH THE SUBSTANCE IS USED OR STORED. ITION TO MAINTAINING AN INVENTORY OR POTENTIALLY TOXIC AND/OR HAZARDOUS MATERIALS AND ASSOCIATED SAFETY INFORMATION, THE FOLLOWING MATERIALS MANAGEMENT PRACTICES ERIALS WILL BE HANDLED IN ACCORDANCE WITH OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REQUIREMENTS AND MANUFACTURER'S INSTRUCTIONS. MICALS REGULATED UNDER THE COMPREHENSIVE ENVIRONMENTAL RESPONSE, COMPENSATIONS AND LIABILITY ACT (CERCLA) WILL BE REPORTED AND HANDLED IN ACCORDANCE WITH EVANT REGULATIONS ERIALS STORED AT THE CONSTRUCTION SITE WILL BE COVERED OR OTHERWISE PROTECTED FROM THE ELEMENTS. QUANTITY OF FUEL AND LUBRICANTS STORED AT THE CONSTRUCTION SITE WILL BE LIMITED TO THE AMOUNT THAT IS RESPONSIBLE TO SUPPORT THE SPECIFIC CONSTRUCTION OR INTENANCE ACTIVITY. OFFSITE STORAGE OF FUEL, HYDRAULIC OIL, AND FORM OIL ARE PREFERABLE. STORAGE AREAS FOR MATERIALS NOT CONSUMED ON A DAILY BASIS ON A DAILY BASIS WILL BE ENCLOSED AND PROTECTED FROM THE ELEMENTS AND CONTAINED IN A MANNER TO VENT RELEASE TO THE ENVIRONMENT. LEUM PRODUCTS AND FERTILIZERS WILL BE STORED AT SEPARATE FACILITIES OR ISOLATED BY IMPERMEABLE BARRIERS. POCHLORITE AND OTHER CHLORINE COMPOUNDS WILL BE STORED SEPARATELY FROM OTHER MATERIALS AND KEPT DRY.

EAS AT THE CONSTRUCTION SITE THAT ARE USED FOR STORAGE OF TOXIC MATERIALS AND PETROLEUM PRODUCTS SHALL BE DESIGNED WITH AN ENCLOSURE, CONTAINER, OR DIKE LOCATED JND THE PERIMETER OF THE STORAGE AREA TO PREVENT DISCHARGE OF THESE MATERIALS IN RUNOFF FROM THE CONSTRUCTION SITE. THESE BARRIERS WILL ALSO FUNCTION TO CONTAIN LED MATERIALS FROM CONTACT WITH SURFACE RUNOFF. WES TO PREVENT SPILLS OR LEAKS OF FUEL, GEAR OIL, LUBRICANTS, ANTIFREEZE, AND OTHER FLUIDS FROM CONSTRUCTION VEHICLES AND HEAVY EQUIPMENT SHALL BE CONSIDERED TO T GROUNDWATER AND RUNOFF QUALITY. ALL EQUIPMENT MAINTENANCE SHALL BE PERFORMED IN A DESIGNATED AREA AND MEASURES, SUCH AS DRIP PANS, SHALL BE USI ITAIN PETROLEUM PRODUCTS, SPILLS OF CONSTRUCTION-RELATED MATERIALS, SUCH AS PAINTS, SOLVENTS, OR OTHER FLUIDS AND CHEMICALS, SHALL BE CLEANED UP IMMEDIATELY AND POSED OR PROPERLY. RETE TRUCKS AND OTHER CONCRETE COATED EQUIPMENT SHALL BE CLEANED ONLY IN DESIGNATED CONCRETE WASHOUT AREAS.

AND OTHER APPLICABLE REGULATIONS. THE SWMP ADMINISTRATOR WILL CARRY OUT THE INSPECTION. BMPs SHALL MATCH THE SWMP BMPs SHALL BE INSTALLED CORRECTLY - THE SEDIMENT BASIN SHALL BE INSPECTED FOR DEPTH OF SEDIMENT, AND BUILT UP SEDIMENT SHALL BE REMOVED BEFORE IT REACHES THE BASINS 50% VOLUME DEPTH AND/OR AT THE COMPLETION OF THE PROJECT

CONCRETE WASH OUT ACTIVITIES.

. CONSTRUCTION WASTE. ADDITIONAL PROVISIONS OF THE EROSION AND SEDIMENT CONTROL PLAN RELATING TO WASTE DISPOSAL ARE AS FOLLOWS: THE CONTRACTOR SHALL REMOVE ALL SEDIMENT, MUD, AND CONSTRUCTION DEBRIS THAT MAY ACCUMULATE IN THE FLOW LINES AND PUBLIC RIGHTS-OF-WAY AS A RESULT OF THE SITE DEVELOPMENT. THIS SHALL BE PERFORMED IN A TIMELY MANNER. THE CONTRACTOR SHALL CONTROL SEDIMENT, DEBRIS, AND ALL OTHER POLLUTANTS FROM ENTERING THE STORM SEWER SYSTEM AS A RESULT OF CONSTRUCTION OPERATIONS.

THE OWNER AND DESIGNATED AGENTS SHALL ENSURE THAT ALL LOADS OF CUT AND FILL MATERIAL IMPORTED OR EXPORTED FROM THE SITE SHALL BE PROPERLY COVERED TO PREVENT LOSS

- BLOW TRASH WILL BE PICKED UP AND DISPOSED OF ON BUILDING SITES AS NECESSARY.
- WHERE POSSIBLE, TRASH BINS WILL BE LOCATED AT LEAST 50 FEET AWAY FROM STORM SEWER INLETS. THEY WILL BE LOCATED IN LEVEL LOCATIONS, BUT NOT IN DRAINAGE PATHS, CURB AND GUTTER, OR ON SIDEWALKS OR DRIVES. DOWNSTREAM PERIMETER CONTROLS SHALL BE INSTALLED TO PREVENT CONTAMINANTS IN STORMWATER FROM ENTERING THE STORM SEWER

8. GROUNDWATER AND STORMWATER DEWATERING. THE DEWATERING OF STORMWATER TO SURFAFCE WATERS FROM EXCAVATIONS IS ALLOWED UNDER THE GENERAL PERMIT (DRPC, 10). THE DEWATERING OF GROUNDWATER OR GROUNDWATER MIXED WITH STORMWATER FROM EXCAVATIONS WILL BE A ALLOWED NON-STORMWATER DISCHARGE PROVIDING THE FOLLOWING CONDITIONS ARE MET: THE SOURCE WATER SHALL NOT CONTAIN POLLUTANTS IN CONCENTRATIONS EXCEEDING THE STATE GROUNDWATER STANDARDS IN REGULATIONS 5 CCR 1002-41 AND 42, PROPER BMPs ARE IMPLEMENTED, AND THESE DISCHARGES ARE TO THE GROUND AND DO NOT LEAVE THE SITE AS SURFACE RUNOFF OR TO SURFACE WATERS.

THE CONTRACTOR SHALL USE AND APPROPRIATE FILTER WHEN PUMPING WATER FROM THE EXCAVATION AND DISCHARGE IN A MANNER THAT DOES NOT CAUSE EROSION OR SURFACE RUNOFF. THIS LAND APPLICATION CAN BE ACCOMPLISHED THROUGH USING AN ENERGY DISSIPATER SUCH AS SPRAYING OVER A LAGE PORTION OF LAND, OR DISCHARGING ONTO RIPRAP WHICH DRAINS INTO A SEDIMENT TRAP. THE SWMP MUST BE UPDATED TO INDICATE LOCATIONS OF DEWATERING LAND APPLICATIONS. IN NO CASE WILL THIS WATER BE ALLOWED INTO FLOW LINES OR OTHERWISE ENTER A STORM SEWER SYSTEM.

THE PERMITTEE MUST APPLY FOR COVERAGE UNDER A SEPARATE CDPS DISCHARGE PERMIT, SUCH AS THE CONSTRUCTION DEWATERING GENERAL PERMIT, IF THERE IS A POTENTIAL FOR

9. BMP SPECIFICATIONS. BMPs SHALL BE IMPLEMENTED, INSTALLED, OPERATED, AND MAINTAINED IN ACCORDANCE WITH THE SPECIFICATIONS.

10. FUGITIVE DUST AND WIND EROSION CONTROLS. EROSION CONTROL MEASURES WILL BE USED TO MITIGATE EROSION CAUSED BY WIND. WATERING EXPOSED, UN-VEGETATED AREAS WITH POTABLE WATER WILL CONTROL FUGITIVE DUST DURING DRY AND WINDY CONDITIONS. SURFACE ROUGHENING, THE USE OF WATERING TRUCKS, AND THE APPLICATION OF BONDED FIBER MATRIX TO DISTURBED AREAS CAN HELP REDUCE FUGITIVE DUST AND WIND EROSION WHILE PERIMETER SILT FENCE WILL HELP CATCH WINDBLOWN SAND AND SOIL.

FINAL STABILIZATION AND LONG-TERM STORMWATER MANAGEMENT

FINAL STABILIZATION OF THE SITE WILL OCCUR WHEN ALL STREETS, WALKS, AND DRIVES ARE PAVED, WHEN ALL GROUND SURFACE DISTURBING ACTIVITIES AT THE SITE HAVE BEEN COMPLETED, AND WHEN A UNIFORM VEGETATIVE COVER HAS BEEN ESTABLISHED WITH A DENSITY OF AT LEAST 70 PERCENT OF PRE-DISTURBANCE LEVELS OR EQUIVALENT PERMANENT PHYSICAL EROSION

PLANNED STRUCTURAL PRACTICES TO CONTROL POLLUTANTS IN STORMWATER DISCHARGES THAT WILL OCCUR AFTER CONSTRUCTION OPERATIONS HAVE BEEN COMPLETED AT THE SITE WILL INCLUDE FINAL LANDSCAPING PER THE LANDSCAPE PLAN, RIPRAP AT DESIGNATED LOCATIONS, AND PERMANENT EROSION CONTROL BLANKETS ALONG VASQUEZ RD AND LIONS GATE DR. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED AND DISPOSED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION IS ACHIEVED, OR AFTER THE TEMPORARY

MEASURES ARE NO LONGER NEEDED, WHICHEVER OCCURS EARLIEST, OR AS AUTHORIZED BY THE LOCAL GOVERNING JURISDICTION. TRAPPED SEDIMENT AND DISTURBED SOIL AREAS RESULTING FROM THE DISPOSAL OF TEMPORARY MEASURES MUST BE RETURNED TO FINAL PLAN GRADES AND PERMANENTLY STABILIZED TO PREVENT FURTHER SOILS EROSION. INSPECTION AND MAINTENANCE

ALL TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE MAINTAINED AND REPAIRED BY THE CONTRACTOR DURING THE CONSTRUCTION PHASES AS NEEDED TO ENSURE CONTINUED PERFORMANCE OF THEIR INTENDED FUNCTION. ALL DISTURBED SURFACE AREAS ARE TO BE STABILIZED IN ACCORDANCE WITH THE APPROVED SWMP/EROSION CONTROL PLAN OR

THE SWMP ADMINISTRATOR, OR THEIR REPRESENTATIVE, SHALL OBSERVE EACH BMP THAT IS SHOWN ON THE APPROVED SWMP/EROSION CONTROL PLAN OR APPROVED AMENDMENTS. THIS REVIEW SHALL INCLUDE COMPLETING AND SIGNING THE "OBSERVATION REPORT" (SEE APPENDIX B) FOR EACH REVIEW DATE. ANY DEVIATIONS FROM THE APPROVED PLAN SHALL BE NOTED ON THE REPORT. THE REVIEWER SHALL ESPECIALLY NOTE ANY BMP THAT IS NOT IN COMPLIANCE WITH THE APPROVED PLAN/APPROVED AMENDMENTS. DEFICIENCIES THAT ARE NOT IMMEDIATELY REPAIRABLE SHOULD BE REPORTED TO THE CONSTRUCTION SUPERINTENDENT, THE OWNER, OR THEIR DESIGNEE FOR INSTRUCTIONS ON HOW TO PROCEED. THE REVIEW SHALL ALSO INCLUDE RECOMMENDED COURSES OF ACTION BASED ON THE FIELD REVIEW. BMPs SHALL BE REVIEWED IN ACCORDANCE WITH THE BMP SPECIFICATIONS AND CRITERIA.

THE CDPS GENERAL PERMIT REQUIRES A THOROUGH STORMWATER MANAGEMENT INSPECTION BE PERFORMED AT LEAST EVERY 14 CALENDAR DAYS, AND WITHIN 24 HOURS AFTER THE NED OF ANY PRECIPITATION OR SNOWMELT EVENT THAT CAUSES SURFACE EROSION WITH THE FOLLOWING EXCEPTIONS:

WHERE NO CONSTRUCTION ACTIVITIES WILL OCCUR FOLLOWING A STORM EVENT, POST STORM EVENT INSPECTIONS SHALL BE CONDUCTED PRIOR TO RE-COMMENCING CONSTRUCTION ACTIVITIES, BUT NO LATER THAN 72 HOURS FOLLOWING THE STORM EVENT. WHERE SNOW COVER EXISTS OVER THE ENTIRE SITE FOR AN EXTENDED PERIOD OF TIME, AND MELTING CONDITIONS DO NOT POSE A RISK OF SURFACE EROSION, THE 14-DAY, MONTHLY, AND POST-STORM EVENT INSPECTIONS ARE NOT REQUIRED. FOR SITES, OR PORTIONS OF SITES, WHERE ALL CONSTRUCTION ACTIVITIES THAT WILL RESULT IN SURFACE GROUND DISTURBANCE ARE COMPLETED AND ALL ACTIVITIES REQUIRED FOR FINAL STABILIZATION, IN ACCORDANCE WITH THIS SWMP, HAVE BEEN COMPLETED, WITH THE EXCEPTION OF SEED THAT HAS NOT OCCURRED DUE TO SEASONAL CONDITIONS OR THE NECESSITY FOR ADDITIONAL SEED APPLICATION TO AUGMENT PREVIOUS EFFORTS, INSPECTIONS WILL BE CONDUCTED AT LEAST ONCE EVERY MONTH AND POST-STORM EVENT INSPECTIONS WILL NOT BE REQUIRED.

FOLLOWING COMPLETION OF THE PROJECT, INCLUDING FINAL RE-VEGETATION AND LANDSCAPING, THE SWMP ADMINISTRATOR WILL INSPECT AREAS THAT HAVE BEEN SEEDED AND LANDSCAPED TO ENSURE THAT THE RE-VEGETATION AND LANDSCAPING HAVE BEEN SUCCESSFUL IN ESTABLISHING UNIFORM GROUND COVER (70% OF PRE-DISTURBANCE COVER CRITERIA FOR RE-VEGETATION). IF RE-VEGETATION HAS NOT BEEN SUCCESSFUL, SPOT RE-VEGETATION OR OTHER REMEDIAL ACTIONS SHOULD BE IMPLEMENTED TO ENSURE COMPLIANCE WITH THE STORMWATER DISCHARGE PERMIT

THE FOLLOWING INSPECTION GUIDELINES AND MAINTENANCE PRACTICES SHOULD BE USED TO CONDUCT WALK AROUND FIELD INSPECTIONS AND TO MAINTAIN EROSION AND SEDIMENT CONTROL BMPs:

BMPs DETAILED ON THE SWMP SHALL BE INSTALLED BMPs SHALL BE APPROPRIATELY APPLIED

WORK PRACTICES SHALL BE EXECUTED TO PRESERVE BMP INSTALLATIONS INSPECT FOR ANY RELEASES OR EVIDENCE OF POSSIBLE PAST OFFISTE RELEASES

- ALL MEASURES SHALL BE MAINTAINED IN GOOD WORKING ORDER. IF A REPAIR IS NECESSARY, IT SHALL BE INITIATED WITHIN 24 HOURS OF THE REPORT
- BUILT UP SEDIMENT SHALL BE REMOVED FROM THE SILT FENCE WHEN IT HAS REACHED ONE—THIRD THE HEIGHT OF THE FENCE, OR THE SILT FENCE IS NO LONGER FUNCTIONING PROPERLY
- BUILT UP SEDIMENT SHALL BE REMOVED FROM STRUCTURAL BMPs WHEN SEDIMENT HAS REACHED ON HALF THE HEIGHT OF THE BMP, OR THE BMP IS NO LONGER FUNCTIONING PROPERLY SILT FENCE SHALL BE INSPECTED FOR DEPTH OF SEDIMENT, TEARS, TO SEE IF THE FABRIC IS SECURELY ATTACHED TO THE FENCE POSTS, AND TO SEE THAT THE FENCE POSTS ARE FIRMLY

A RAIN GAUGE WILL BE REQUIRED ONSITE TO DETERMINE THE AMOUNT OF PRECIPITATION RECEIVED ON THE SITE. ITS LOCATION WILL BE DECIDED ONSITE.

COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENTAL GUIDELINES, WATER QUALITY CONTROL DIVISION, DENVER, COLORADO, MAY 1995 DIVISION RESPONSE TO PUBLIC COMMENTS - PART 2, STORMWATER CONSTRUCTION GENERAL PERMIT COR-030000, COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT, WATER

QUALITY CONTROL DIVISION, DENVER, COLORADO, MAY 2007. 3. URBAN STORM DRAINAGE CRITERIA MANUAL, VOLUME 3, URBAN DRAINAGE AND FLOOD CONTROL DISTRICT, DENVER, COLORADO, SEPTEMBER 1999.





				CF
				Ву
				Date
				No. Revision
				No.


<u>R</u>


Scale: AS NOTED Date: 8/5/24 Job No. WPTH-01 File No.


Sheet C-2.0





























Design Practice Inc 2842 W. 44<sup>th</sup> Ave







THE LANDINGS

Scale: AS NOTED


Date: 8/5/24

Job No. WPTH-01

File No.

Sheet C-4.1

Silt Fence (SF) **SC-1** 



SILT FENCE POSTS SHALL OVERLAP AT JOINTS SO THAT NO GAPS 7 EXIST IN SILT FENCE POSTS SHALL BE JOINED AS THICKNESS OF GEOTEXTILE HAS SHOWN, THEN ROTATED 180 DEG. BEEN EXAGGERATED, TYP IN DIRECTION SHOWN AND DRIVEN INTO THE GROUND SECTION A

SF-1. SILT FENCE

November 2010

**Stockpile Management (SP)** 

Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3

**STOCKPILE** 

STOCKPILE PROTECTION PLAN

SECTION A

SP-1. STOCKPILE PROTECTION

2. INSTALL PERIMETER CONTROLS IN ACCORDANCE WITH THEIR RESPECTIVE DESIGN DETAILS.

SILT FENCE IS SHOWN IN THE STOCKPILE PROTECTION DETAILS; HOWEVER, OTHER TYPES OF

TYPE OF PERIMETER CONTROL FOR A STOCKPILE INCLUDE WHETHER THE STOCKPILE IS LOCATED ON A PERVIOUS OR IMPERVIOUS SURFACE, THE RELATIVE HEIGHTS OF THE PERIMETER CONTROL AND STOCKPILE, THE ABILITY OF THE PERIMETER CONTROL TO CONTAIN THE STOCKPILE WITHOUT FAILING IN THE EVENT THAT MATERIAL FROM THE STOCKPILE SHIFTS

3. STABILIZE THE STOCKPILE SURFACE WITH SURFACE ROUGHENING, TEMPORARY SEEDING AND

EXTENDED PERIOD (TYPICALLY FOR MORE THAN 60 DAYS) SHOULD BE SEEDED AND MULCHED

4. FOR TEMPORARY STOCKPILES ON THE INTERIOR PORTION OF A CONSTRUCTION SITE, WHERE

OTHER DOWNGRADIENT CONTROLS, INCLUDING PERIMETER CONTROL, ARE IN PLACE, STOCKPILE

MULCHING, EROSION CONTROL BLANKETS, OR SOIL BINDERS. SOILS STOCKPILED FOR AN

WITH A TEMPORARY GRASS COVER ONCE THE STOCKPILE IS PLACED (TYPICALLY WITHIN 14 DAYS). USE OF MULCH ONLY OR A SOIL BINDER IS ACCEPTABLE IF THE STOCKPILE WILL BE

PERIMETER CONTROLS INCLUDING SEDIMENT CONTROL LOGS OR ROCK SOCKS MAY BE SUITABLE IN SOME CIRCUMSTANCES. CONSIDERATIONS FOR DETERMINING THE APPROPRIATE

STOCKPILE PROTECTION INSTALLATION NOTES

-TYPE OF STOCKPILE PROTECTION.

PERIMETER CONTROLS MAY NOT BE REQUIRED.

OR SLUMPS AGAINST THE PERIMETER, AND OTHER FACTORS.

IN PLACE FOR A MORE LIMITED TIME PERIOD (TYPICALLY 30-60 DAYS).

SEE PLAN VIEW FOR:
 -LOCATION OF STOCKPILES.

SF-3

MM-2

SILT FENCE (SEE SF DETAIL FOR

INSTALLATION REQUIREMENTS)

SILT FENCE (SEE SF DETAIL FOR INSTALLATION REQUIREMENTS)

**Vehicle Tracking Control (VTC)** 

IP-4

**SC-6** 

SOCKS

CURB SOCK -

**SM-4** 

August 2013

**Inlet Protection (IP)** 

SEE ROCK SOCK DESIGN

16" CINDER

IP-1. BLOCK AND ROCK SOCK SUMP OR ON GRADE

INLET PROTECTION

2. CONCRETE "CINDER" BLOCKS SHALL BE LAID ON THEIR SIDES AROUND THE INLET IN A

SINGLE ROW, ABUTTING ONE ANOTHER WITH THE OPEN END FACING AWAY FROM THE CURB.

3. GRAVEL BAGS SHALL BE PLACED AROUND CONCRETE BLOCKS, CLOSELY ABUTTING ONE

3'-5' TYP.

IP-2. CURB ROCK SOCKS UPSTREAM OF

INLET PROTECTION

2. PLACEMENT OF THE SOCK SHALL BE APPROXIMATELY 30 DEGREES FROM PERPENDICULAR

3. SOCKS ARE TO BE FLUSH WITH THE CURB AND SPACED A MINIMUM OF 5 FEET APART.

4. AT LEAST TWO CURB SOCKS IN SERIES ARE REQUIRED UPSTREAM OF ON-GRADE INLETS.

Urban Drainage and Flood Control District

Urban Storm Drainage Criteria Manual Volume 3

ANOTHER AND JOINTED TOGETHER IN ACCORDANCE WITH ROCK SOCK DESIGN DETAIL.

2"x4" WOOD STUD -

BLOCK AND ROCK SOCK INLET

9 2

BLOCKS

DETAIL FOR JOINTING

2"x4" WOOD

BLOCK AND CURB SOCK INLET PROTECTION INSTALLATION NOTES

SOCKS APPROX 30 DEG.


CURB ROCK SOCK INLET PROTECTION INSTALLATION NOTES

IN THE OPPOSITE DIRECTION OF FLOW.

1. SEE ROCK SOCK DESIGN DETAIL INSTALLATION REQUIREMENTS.

MINIMUM ÖF TWO CURB

1. SEE ROCK SOCK DESIGN DETAIL FOR INSTALLATION REQUIREMENTS.




VTC-1. AGGREGATE VEHICLE TRACKING CONTROL

November 2010 Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 VTC-3

**Concrete Washout Area (CWA)** 

CONCRETE WASHOUT VEHICLE TRACKING CONTROL (SEE VTC DETAIL) OR OTHER STABLE SURFACE



CWA-1. CONCRETE WASHOUT AREA

CWA INSTALLATION NOTES

SEE PLAN VIEW FOR:
 -CWA INSTALLATION LOCATION.

2. DO NOT LOCATE AN UNLINED CWA WITHIN 400' OF ANY NATURAL DRAINAGE PATHWAY OR WATERBODY. DO NOT LOCATE WITHIN 1,000' OF ANY WELLS OR DRINKING WATER SOURCES. IF SITE CONSTRAINTS MAKE THIS INFEASIBLE, OR IF HIGHLY PERMEABLE SOILS EXIST ON SITE, THE CWA MUST BE INSTALLED WITH AN IMPERMEABLE LINER (16 MIL MIN. THICKNESS) OR SURFACE STORAGE ALTERNATIVES USING PREFABRICATED CONCRETE WASHOUT DEVICES OR A LINED ABOVE GROUND STORAGE ARE SHOULD BE USED.

3. THE CWA SHALL BE INSTALLED PRIOR TO CONCRETE PLACEMENT ON SITE.

4. CWA SHALL INCLUDE A FLAT SUBSURFACE PIT THAT IS AT LEAST 8' BY 8' SLOPES LEADING OUT OF THE SUBSURFACE PIT SHALL BE 3:1 OR FLATTER. THE PIT SHALL BE AT

5. BERM SURROUNDING SIDES AND BACK OF THE CWA SHALL HAVE MINIMUM HEIGHT OF 1'.

6. VEHICLE TRACKING PAD SHALL BE SLOPED 2% TOWARDS THE CWA.

7. SIGNS SHALL BE PLACED AT THE CONSTRUCTION ENTRANCE, AT THE CWA, AND ELSEWHERE AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CWA TO OPERATORS OF CONCRETE TRUCKS AND PUMP RIGS.

8. USE EXCAVATED MATERIAL FOR PERIMETER BERM CONSTRUCTION.


November 2010

Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 CWA-3

**MM-1** 

**Stabilized Staging Area (SSA)** 

**SM-6** 



SSA-1. STABILIZED STAGING AREA

STABILIZED STAGING AREA INSTALLATION NOTES

1. SEE PLAN VIEW FOR

-LOCATION OF STAGING AREA(S). -CONTRACTOR MAY ADJUST LOCATION AND SIZE OF STAGING AREA WITH APPROVAL FROM THE LOCAL JURISDICTION.

2. STABILIZED STAGING AREA SHOULD BE APPROPRIATE FOR THE NEEDS OF THE SITE. OVERSIZING RESULTS IN A LARGER AREA TO STABILIZE FOLLOWING CONSTRUCTION.

3. STAGING AREA SHALL BE STABILIZED PRIOR TO OTHER OPERATIONS ON THE SITE.

4. THE STABILIZED STAGING AREA SHALL CONSIST OF A MINIMUM 3" THICK GRANULAR

5. UNLESS OTHERWISE SPECIFIED BY LOCAL JURISDICTION, ROCK SHALL CONSIST OF DOT SECT. #703, AASHTO #3 COARSE AGGREGATE OR 6" (MINUS) ROCK. 6. ADDITIONAL PERIMETER BMPs MAY BE REQUIRED INCLUDING BUT NOT LIMITED TO SILT

STABILIZED STAGING AREA MAINTENANCE NOTES

FENCE AND CONSTRUCTION FENCING.

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE, INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.

2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE

3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON

4. ROCK SHALL BE REAPPLIED OR REGRADED AS NECESSARY IF RUTTING OCCURS OR UNDERLYING SUBGRADE BECOMES EXPOSED.

November 2010

Urban Storm Drainage Criteria Manual Volume 3

SSA-3

<sup>≿`</sup>8/5/24` 34357

> Nand land a in

ANDIN

Scale: NONE **Date:** 8/5/24 Job No. WPTH-01 File No.


Sheet C-5.0


November 2010

Urban Drainage and Flood Control District Urban Storm Drainage Criteria Manual Volume 3 SP-3

Urban Drainage and Flood Control District









CONNECTED BY LOCKABLE/SEALABLE CONNECTORS TO MANUFACTURERS SPECIFICATIONS.


GRAND COUNTY WATER


AND SANITATION DISTRICT #1


DATE: OCT 6, 2021































DATE: Aug 31, 2022


No: W—7a


File No.


Sheet C-5.2














					Date By	Checked By: CCF
					No. Revision	Designed By: CCF Che
EABRE ENINGING. civil, municipal, urban, land development 2063 Pinon Place Erie, CO 80516 720-903-0048						

ANDIN

Scale: NONE


**Date:** 8/5/24


File No.

Job No. WPTH-01

Sheet C-5.3









Standard Details Fig 17 May 2012

DATE 5/1/2012

FILENAME: FIG 17 - TYPE13.DWG




DATE 5/1/2012 FILENAME: FIG 4 - CURB & GUTTER.DWG



Standard Details Fig 15 May 2012

DATE: 5/1/2012





ERIN Jan, land dev

ANDIN THE

Scale: NONE **Date:** 8/5/24 Job No. WPTH-01 File No.

Sheet C-5.4

FILENAME: FIG 15 - PIPE BEDDING.DWG

